



Nr. 1377/7 prot.

Kamëz, më 10.06.2024

PREVENTIV

Objekti : Rehabilitim Kun-je Rr Argjinatura deri te Azili i Pleqve (Rr Teuta)

NR.	An.	EMERTIMI	NJESIA	SASIA	ÇMIMI	VLERA
LINJE KUN-je						
I Punime Shpyllezimi ,prishje e Transporti						
1	3.2	Prerje bime te vogla Ø ~ 10cm	m ²	2,416		
2	3.3	Prerje e sistemim pemesh Ø 10 ~ 20 cm	copë	150		
3	3.7	Shkulje rrenjeve bimeve te vogla	m ²	2,416		
4	2.426/3	Prishje shtresa betoni(Kuneta ekzistuese betoni tip kolektori)	m ³	20		
5	2.426/5	Prishje mure betoni	m ³	12		
6	3.158/5a	Transport materiale te ndryshme me auto deri 5.0 km	m ³	500		
SHUMA I						
II Punime Germimi						
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	2,928		
2	3.47/1b	Mbushje, rafshim,ngjeshje me tokmak elektrik, cdo 30 cm, toke te zakonshme (pjesa e dheut te shkrifet te germuar)	m ³	1,562		
3	3.161	Rrafshim skarpate ne germim, ekskavator 1 m3 (skarifikim)	m ³	1,558		
4	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	258		
SHUMA II						
III Punime Shtresash						
1	4.19	Prerje asfalti me disk, ne te dy anet.	ml	13		
2	3.969	Skarifikim shtrese asfalti ekzistues me makineri	m ²	30		
3	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri pjesa e kolektorit t=10cm	m ³	423		
4	3.209	Shtrese çakelli mbeturine kave t=10cm, perhapur e ngjeshur me makineri Rruga mbi kolektor B=5m	m ²	5,703		
5	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri (tek nderhyrjet ne asfalt)	m ²	30		
6	3.221/1	Shtrese binderi me granil gur kave,4cm,me makineri	m ²	30		
7	3.226/3	Shtrese asfaltobetoni me granil guri kave, 6cm, me makineri	m ²	30		
SHUMA III						
IV Ndertimi i Veprave te Artit+Kanalizime						
1	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	596		
2	3.366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	ml	612		
3	3.584	Ndertim Pusete kontrolli b/a, 1x1xH=2÷2.5m me kapak gize Klasi:D400 - max 40 ton	cope	17		
4	3.642	Ndertim puseta betoni b/a 1.5x1.5 H=2÷2.5+kapak gize Klasi:D400 - max 40 ton	cope	19		
5	2.523/1	F.V Tuba PVC f=200 mm te brinjezuar per lidhje familjare	ml	60		
6	2.275	Shtrese betoni C16/20 me zgare hekuri (Mbeshtjellje e lidhjes)	m ³	2		
SHUMA IV						
SHUMA I-IV						
TVSH 20%						
SHUMA TOTALE E OBJEKTIT						

Shenim: Tubat e betonit D=600mm dhe 800mm do te zbriten si çmim pasi jane siguruar nga FSHZH-ja
Tek analiza 3.365&3.366 jane te gjitha zerat e punes duke hequr vetem tubin

Preventivues
Ing. Bardhok Alia

Ing. Edison Kolgjini

Ing. Dritan Nuzi

