



"ANGERBA" sh.p.k.

**RIKONSTRUKSION SHKARKUESI
KATASTROFIK MALAJ-1**

BASHKIA MIRDITE

PROJEKT ZBATIMI

PREVENTIVI

QERSHOR 2024

"ANGERBA"shpk



OBJEKTI: "RIKONSTRUKSION SHKARKUESI KATASTROFIK MALAJ 1"
BASHKIA MIRDITE

Nr.	NR. ANALIZE	EMERTIMI I PUNIMIT	NJESIA	SASIA	CMIMI	VLEFTA
1 Riparimi i Shkarkuesit						
1	3.183/c	Shtrese zhavorr lumi t=20 cm, per Piketen 1-2	m ²	50		
2	2.262/4	Shtrese betoni C16/20 per Piketen 1-2	m ³	11.01933		
3	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.55		
4	3.405/1	Prishje struktura prej betoni (Pk.7-16)	m ³	100		
5	3.87/b	Germim dheu me ekskavator goma, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne toke	m ³	508		
6	3.183/a	Shtrese zhavorr lumi t=10 cm (nen lugun b/a)	m ²	271		
7	3.24	Shtrese betoni C12/15, t= 10 cm (nen lugun b/a)	m ³	27		
8	3.244/1	Struktura te holla monolite betoni C 20/25 (per lugun b/a)	m ³	134		
9	2.166	F V hekur betoni periodik Ø 6 - 10 mm (per lugun)	ton	8.20		
10	2.166/1a	F V hekur betoni periodik Ø > 12 mm (per lugun)	ton	0.226		
11	2.19	Hedhje, rrafshim, mbushje dheu me krah, kategoria III	m ³	213		
12	An.1	Ndertim drenazhi, mbushje me zall te lare lavatriçe	m ³	187		
13	3.401/1	Gjeotekstil me gramature 280 g/m ²	m ²	753		
14	3.406	F V tub drenazhi Ø 150 mm	ml	150		
Shuma 1						
2 Pusi i Shuarjes se Energjise						
1	3.87/b	Germim dheu me ekskavator goma, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne toke	m ³	350		
2	3.183/a	Shtrese zhavorr lumi t=10 cm (nen murin b/a)	m ²	79		
3	3.24	Shtrese betoni C12/15, t= 5 cm (nen murin b/a)	m ³	4		
4	3.396/1	Mbushje me zhavorr pas mureve (nen pusin e shuarjes)	m ³	35		
5	3.245/1	Struktura te holla monolite betoni C 25/30	m ³	88		
6	2.166	F V hekur betoni periodik Ø 6 - 10 mm (per murin)	ton	0.28		
7	2.166/1a	F V hekur betoni periodik Ø > 12 mm (per murin)	ton	7.030		
8	3.243/1	Struktura te holla monolite betoni C 16/20 (per shuares)	m ³	33		
9	3.243/1	Struktura te holla monolite betoni C 16/20 (per muret anesore)	m ³	13		
10	2.166	F V hekur betoni periodik Ø 6 - 10 mm (per shuaresin)	ton	0.89		
11	3.331	Gabiona me rrjete teli te zinguar e gure kave 1x1x1 m	m ³	40		
12	3.332	Gabiona me rrjete teli te zinguar, gure kave 1x1x1.5 m	m ³	45		
13	3.396/1	Mbushje me zhavorr pas mureve (muret b/a)	m ³	140		
14	3.243/1	Struktura te holla monolite betoni C 16/20 (per shtresen e sipërme t=30 cm)	m ³	13		
Shuma 2						

SHUMA PA TVSH (1+2) 10 000 000
TVSH (20%)
TOTALI

"ANGERBA"shpk
Ing. Burhan HAFIZI



OBJEKTI: "RIKONSTRUKSION SHKARKUESI KATASTROFIK MALAJ 1"
ANALIZA TEKNIKE TE ÇMIMEVE

Nr. Analize	EMERTIMI	Njesia	PUNTORI			TRANSPORT			MAKINERI			MATERIAL			Shuma	Shp pl 8%	Fitim 10%	TOTALI
			op	çmimi	Vlefa	T/km	çmimi	Vlefa	o.p	çmin	Vlefa	Sasia	çmimi	Vlefa				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
An.1	Ndertim drenazhi, mbushje me zall te lare lavatrice	m ³																
	Sp + p (Paga+Kontributet)	op	4.1															
	Zall i lare ne lavatrice	m ³				17						1.1						
	Shuma :																	

PROJEKTUESI
 "ANGERBA" shpk

