



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

OBJEKTI: Ndertim Rruget Blloku 3 Bathore 7

OBJEKTI : Ndertim Rruga "Zapod" Bathore7

(L =215ml, basf= 4m,)

I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	86		
2	3.158/5a	Transport dheu me auto 5km	m ³	86		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	103.2		
4	3.211	Shtrese çakelli T=20cm	m ²	860		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	860		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	860		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	860		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	480		
9	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	4		
10	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
SHUMA I						

OBJEKTI : Ndertim Rruga "Kol Idromeno" Bathore7

(L =215ml, basf= 4m, KUZ -D=315mm)

I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	86		
2	3.158/5a	Transport dheu me auto 5km	m ³	86		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	103.2		
4	3.211	Shtrese çakelli T=20cm	m ²	860		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	860		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	860		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	860		
8	2,111	Mure betoni C12/15(themel,xokol betoni)	m ³	35.2		
9	3.288	F.V Hekur betoni I zakonshem O > 12 mm	ton	0.96		
10	2.426/2	Prishje mure me blloqe + transport	m ³	64		
11	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	480		
12	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
SHUMA I						
II						
PUNIME NE KUZ						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	206.4		
2	3.158/5a	Transport dheu me auto 5km	m ³	206.4		
3	3.396	Mbushje me cakell pas mureve	m ³	186		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	211		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	4		
SHUMA II						

SHUMA I-II						
OBJEKTI : Ndertim Rruga "Frang Bardhi" Bathore7						
(L =217ml, basf= 4m,)						
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	86.8		
2	3.158/5a	Transport dheu me auto 5km	m ³	86.8		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	86.8		
4	3.211	Shtrese çakelli T=20cm	m ²	868		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	868		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	868		
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	868		
8	2,111	Mure betoni C12/15(themel,xokol betoni)	m ³	35.2		
9	3.288	F.V Hekur betoni I zakonshem O > 12 mm	ton	0.96		
10	2.426/2	Prishje mure me blloqe + transport	m ³	64		
11	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+viejzime kembesoret	ml	484		
12	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	5		
13	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
SHUMA I						
OBJEKTI : Ndertim Rruga "Gjon Buzuku" Bathore7						
(L =217ml, B=5ml, basf= 4m, +0.5mKUB ,bankine, KUB -D=315mm)						
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	97.65		
2	3.158/5a	Transport dheu me auto 5km	m ³	97.65		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	118.482		
4	3.211	Shtrese çakelli T=20cm	m ²	868		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	868		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	868		
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	868		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+viejzime kembesoret	ml	484		
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
SHUMA I						
II PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	208.32		
2	3.158/5a	Transport dheu me auto 5km	m ³	208.32		
3	3.396	Mbushje me cakell pas mureve	m ³	191		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	217		
5	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	8		
SHUMA III						
SHUMA I-II						
OBJEKTI : Ndertim Rruga "Jeronim De Rada" Bathore7						
(L =213ml, B=5ml, basf= 4m, 0.5m bankine ne dy anet)						
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	106.5		
2	3.158/5a	Transport dheu me auto 5km	m ³	106.5		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	106.5		
4	3.211	Shtrese çakelli T=20cm	m ²	852		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	852		

6	3.222/1	Shtrese binderi 1x5 cm	m ²	852		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	852		
8	2,111	Mure betoni C12/15(themel,xokol betoni)	m ³	93.72		
9	3.288	F.V Hekur betoni I zakonshem O > 12 mm	ton	2.5		
10	2.426/2	Prishje mure me blloqe + transport	m ³	170.4		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	476		
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
			SHUMA I			

OBJEKTI : Ndertim Rruga "Syri kalter +seg.1" Bathore7

(L =215+57=272ml, B=4.5ml, basf= 4m,+0.5m kub , KUB -D=315mm)

I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	122.4		
2	3.158/5a	Transport dheu me auto 5km	m ³	122.4		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	122.4		
4	3.211	Shtrese çakelli T=20cm	m ²	1088		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1088		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	1088		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	1088		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	594		
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
			SHUMA I			

II PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	326.4		
2	3.158/5a	Transport dheu me auto 5km	m ³	326.4		
3	3.396	Mbushje me cakell pas mureve	m ³	302		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	269		
5	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	9		
			SHUMA II			
			SHUMA I-II			

OBJEKTI : Ndertim Rruga "Hena Neptuni" Bathore7

(L =150ml, B=5ml, basf= 4m,)

I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	60		
2	3.158/5a	Transport dheu me auto 5km	m ³	60		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	60		
4	3.211	Shtrese çakelli T=20cm	m ²	600		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	600		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	600		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	600		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	350		
9	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	4		
10	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
			SHUMA I			

OBJEKTI : Ndertim Rruga "Helmut Kol" Bathore7

(L =110ml, basf= 4m,)

I	PUNIME NE RRUGE					
NR.	Nr.Än	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	44		
2	3.158/5a	Transport dheu me auto 5km	m ³	44		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m ³	67.26		
4	3.211	Shtrese çakelli T=20cm	m ²	440		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	440		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	440		
7	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m ²	440		
8	2,111	Mure betoni C12/15(themel,xokol betoni)	m ³	15.6		
9	3.288	F.V Hekur betoni I zakonshem O > 12 mm	ton	0.36		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	410		
9	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Ø 1.0 m	cope	5		
10	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	2		
		SHUMA I				
		TOTALI				
		TVSH 20%				
		TVSH TOTALE				

Preventivues:

Ing. Eglantina Disha



Drejtori P.I-se

Ing. Flora MUÇA



MIRATOI
Rakip SULI

KRYETAR

