



**REPUBLIKA E SHQIPERISE**  
**BASHKIA KAMEZ**  
**PREVENTIV**

**OBJEKTI : Ndertim blloku Rrugesh ne Lagjen Kamez 5**

**OBJEKTI : Ndertim Rruga "BURIMI" Kamez 5**

**( L =210ml, B=5ml, basf= 4m, 0.5m bankine ne dy anet, KUZ -D=315mm)**

<b>I</b>						
<b>PUNIME NE RRUGE</b>						
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	112.5		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	112.5		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m <sup>3</sup>	135		
4	3.211	Shtrese çakelli T=20cm	m <sup>2</sup>	900		
5	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	900		
6	3.222/1	Shtrese binderi 1x5 cm	m <sup>2</sup>	900		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m <sup>2</sup>	900		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor ).Termoplastike (paste ) anesoret + aksi+vije zime kembesoret	ml	500		
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	3		
<b>SHUMA I</b>						
<b>II</b>						
<b>PUNIME NE KUZ</b>						
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	270		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	270		
3	3.396	Mbushje me cakell pas mureve	m <sup>3</sup>	217		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm ( perfshire reren per mbrojtjen e tubit )	ml	221		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	5		
<b>SHUMA II</b>						
<b>SHUMA I-II</b>						

**Ndertim Rruga "GUCIA" Kamez 5**

**( L =230ml, B=5ml, basf= 4m, 0.5m bankine ne dy anet, KUZ -D=315mm)**

<b>I</b>						
<b>PUNIME NE RRUGE</b>						
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	72.5		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	72.5		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m <sup>3</sup>	87		
4	3.211	Shtrese çakelli T=20cm	m <sup>2</sup>	580		
5	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	580		
6	3.222/1	Shtrese binderi 1x5 cm	m <sup>2</sup>	580		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m <sup>2</sup>	580		
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor ).Termoplastike (paste ) anesoret + aksi+vije zime kembesoret	ml	340		
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	3		

II		PUNIME NE KUZ					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA			
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	139.2			
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	139.2			
3	3.396	Mbushje me cakell pas mureve	m <sup>3</sup>	118			
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm ( perfshire reren per mbrojtjen e tubit )	ml	142			
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	3			
			SHUMA II				
			SHUMA I-II				
Ndertim Rruga "Faik Hoxhaj (ish Miqesia)+3pingulet me Faik Hoxhen" Kamez 5 ( L =430ml+80+140+100, B=5ml, basf= 4m, 0.5m bankine ne dy anet, KUZ -D=315mm)							
I		PUNIME NE RRUGE					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA	
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	385			
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	385			
3	3.164/1b	Mbushje me cakell shkembor+bankine	m <sup>3</sup>	462			
4	3.211	Shtrese cakelli T=20cm	m <sup>2</sup>	3080			
5	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	3080			
6	3.222/1	Shtrese binderi 1x5 cm	m <sup>2</sup>	3080			
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m <sup>2</sup>	3080			
8	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor ).Termoplastike (paste ) anesoret + aksi+vijeizime kembesoret	ml	1620			
9	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	8			
			SHUMA I				
II		PUNIME NE KUZ					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA	
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	378.4			
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	378.4			
3	3.396	Mbushje me cakell pas mureve	m <sup>3</sup>	330			
5	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm ( perfshire reren per mbrojtjen e tubit )	ml	422			
6	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	8			
			SHUMA II				
			SHUMA I-II				
			TOTALE				
			TVSH 20%				
			TVSH TOTALE				

**Preventivues:**

Ing. Eglantina Disha



Drejtori P.I-se

Ing. Flora MUÇA



**KRYETAR**