

"ANGERBA" shpk

PREVENTIV

OBJEKTI : "SISTEMIM ASFALTIM I RRUGES SE MALESOREVE"

BASHKIA VAU DEJES

PREVENTIVI PERMBLEDHES

NR	EMERTIMI I N/OBJEKTIT	NJESIA	VLEFTA
I	RRUGA KRYESORE ; L = 212 ml	Leke	
II	DEGEZIMI I DJATHTE ; L = 280 ml	Leke	
III	DEGEZIMI I MAJTE ; L = 156 ml	Leke	
	SHUMA	Leke	
	TVSH 20 %	Leke	
	TOTALI	Leke	

Shenim Preventivi eshte vleresuar me Sistemit te Integruar te Manualit te Çmimeve bazuar ne V.K.M.
Nr. 216 ,date 13.04.2023

"ANGERBA" shpk
Ing.Burhan HAFIZI



"ANGERBA" shpk

PREVENTIV

OBJEKTI : "SISTEMIM ASFALTIM I RRUGES SE MALESOREVE;
NJESIA ADMINISTRATIVE BUSHAT"

BASHKIA VAU DEJES

I.RRUGA KRYESORE ; L = 212 ml

Nr	Nr.An.	Zeri i punes	Njesia	Sasia	Çmimi	Vlefta
1.PUNIME DHEU						
1	3.2	Prerje bime te vogla Ø deri 10 cm	m ²	852		
2	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	307		
3	3.158/4a	Transport dheu me auto deri 4.0 km	m ³	307		
4	3.95/a	Germim dheu me ekskavator zingjir 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m ³	99		
5	3.47/1b	Mbushje, rafshim,ngjeshje me tokmak elektrik, cdo 30 cm, toke te zakonshme	m ³	99		
SHUMA 1						
2.PUNIME BETONI DHE VEPRA ARTI						
1	3.183/a	Shtrese zhavor lumi t=10cm, nen beton	m ²	332		
2	3.237	Struktura monolite b/betoni C 12/15 me 25% gur per mure mbajtes	m ³	184		
3	3.243/1	Struktura te holla monolite betoni C 16/20, per lug	m ³	28		
4	3.243/1	Struktura te holla monolite betoni C 16/20, per veshjen e kanalit	m ³	9		
5	3.396/1	Mbushje me zhavorr pas mureve	m ³	167		
6	AN.I	Tombino Ø 60 cm,L = 15 ml	cope	1		
7	AN.II	Tombino Ø 60 cm,L = 8 ml	cope	1		
SHUMA 2						
3.PUNIME PER SHTRESA RRUGORE						
1	3.212/c	Shtrese stabilizant 15 cm	m ²	740		
2	3.229/1	Shtrese binder zall lavatriçe 5 cm me makineri	m ²	740		
3	3.231/1	Shtrese asfaltobeton zall lavatriçe 3 cm me makineri	m ²	740		
4	3.212/b	Shtrese stabilizant t=10 cm per bankine	m ²	212		
SHUMA 3						
SHUMA I (1+2+3)						

"ANGERBA" shpk

Ing.Burhan HAFIZI



Analiza I

Tombino Ø 60 cm L = 15 ml

Nr	Nr.An.	Zeri i punes	Njesia	Sasia	Çmimi	Vlefta
1	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m ³	40		
2	3.183/a	Shtrese zhavor lumi t=10cm, per nenshtrese	m ²	3		
3	3.243	Struktura monolite betoni C 16/20 per mure	m ³	3		
4	3.243	Struktura monolite betoni C 16/20 per shtrese mbi tuba, t= 20 cm	m ³	5		
5	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	15		
6	3.396/1	Mbushje me zhavorr pas mureve	m ³	6		
		SHUMA				

Analiza II

Tombino Ø 60 cm L = 8 ml

Nr	Nr.An.	Zeri i punes	Njesia	Sasia	Çmimi	Vlefta
1	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m ³	22		
2	3.183/a	Shtrese zhavor lumi t=10cm, per nenshtrese	m ²	3		
3	3.243	Struktura monolite betoni C 16/20 per mure	m ³	3		
4	3.243	Struktura monolite betoni C 16/20 per shtrese mbi tuba, t= 20 cm	m ³	2		
5	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	8		
6	3.396/1	Mbushje me zhavorr pas mureve	m ³	4		
		SHUMA				

"ANGERBA" shpk
Ing.Burhan HAFIZI



II.DEGEZIMI I DJATHTE ; L = 280 ml

<i>Nr</i>	<i>Nr.An.</i>	<i>Zeri i punes</i>	<i>Njesia</i>	<i>Sasia</i>	<i>Çmimi</i>	<i>Vlefta</i>
1.PUNIME DHEU						
1	3.2	Prerje bime te vogla Ø deri 10 cm	m ²	480		
2	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	560		
3	3.158/4a	Transport dheu me auto deri 4.0 km	m ³	560		
4	3.95/a	Germim dheu me ekskavator zingjir 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m ³	197		
5	3.47/1b	Mbushje, rafshim,ngjeshje me tokmak elektrik, cdo 30 cm, toke te zakonshme	m ³	197		
SHUMA 1						
2.PUNIME BETONI DHE VEPRA ARTI						
1	3.183/a	Shtrese zhavor lumi t=10cm, nen beton	m ²	297		
2	3.243/1	Struktura te holla monolite betoni C 16/20, per mur betoni	m ³	58		
3	3.243/1	Struktura te holla monolite betoni C 16/20, per kanalin anesor	m ³	105		
4	AN.III	Tombino Ø 50 cm,L = 5 ml	cope	1		
SHUMA 2						
3.PUNIME PER SHTRESA RRUGORE						
1	3.212/c	Shtrese stabilizant 15 cm	m ²	1079		
2	3.229/1	Shtrese binder zall lavatriçe 5 cm me makineri	m ²	811		
3	3.231/1	Shtrese asfaltobeton zall lavatriçe 3 cm me makineri	m ²	811		
4	3.212/b	Shtrese stabilizant t=10 cm per bankine	m ²	268		
SHUMA 3						
SHUMA II (1+2+3)						

Analiza III

Tombino Ø 50 cm L = 5 ml

<i>Nr</i>	<i>Nr.An.</i>	<i>Zeri i punes</i>	<i>Njesia</i>	<i>Sasia</i>	<i>Çmimi</i>	<i>Vlefta</i>
1	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m ³	16		
2	3.183/a	Shtrese zhavor lumi t=10cm, per nenshtrese	m ²	2		
3	3.243	Struktura monolite betoni C 16/20 per mure	m ³	3		
4	3.243	Struktura monolite betoni C 16/20 per shtrese mbi tuba, t= 20 cm	m ³	2		
5	3.364	F.V. tub betoni Ø 500 ml shtrese betoni	ml	5		
6	3.396/1	Mbushje me zhavorr pas mureve	m ³	4		
SHUMA						



"ANGERBA" shpk
Ing.Burhan HAFIZI

III.DEGEZIMI I MAJTE ; L = 156 ml

<i>Nr</i>	<i>Nr.An.</i>	<i>Zeri i punes</i>	<i>Njesia</i>	<i>Sasia</i>	<i>Çmimi</i>	<i>Vlefta</i>
1.PUNIME DHEU						
1	3.2	Prerje bime te vogla Ø deri 10 cm	m ²	620		
2	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	301		
3	3.158/4a	Transport dheu me auto deri 4.0 km	m ³	301		
4	3.95/a	Germim dheu me ekskavator zingjir 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m ³	72		
5	3.47/1b	Mbushje, rafshim,ngjeshje me tokmak elektrik, cdo 30 cm, toke te zakonshme	m ³	72		
SHUMA 1						
2.PUNIME BETONI DHE VEPRA ARTI						
1	3.183/a	Shtrese zhavor lumi t=10cm, nen beton	m ²	171		
2	3.243/1	Struktura te holla monolite betoni C 16/20, per murin dhe kanal in anesor	m ³	94		
SHUMA 2						
3.PUNIME PER SHTRESA RRUGORE						
1	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri	m ²	332		
2	3.183/a	Shtrese zhavor lumi t=10cm, nen beton	m ²	332		
3	3.243/1	Struktura te holla monolite betoni C 16/20, per Shtrese B/A, tmes=13 cm	m ³	65		
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm cdo 20 cm	ton	0.528		
5	3.212/b	Shtrese stabilizant t=10 cm per bankine	m ²	71		
SHUMA 3						
SHUMA II (1+2+3)						

"ANGERBA" shpk
Ing.Burhan HAFIZI

