

Projektuesi: Jonida goga
Objekti: Rikonstruksion i rruges karrec

Datë: 01-05-2024

PREVENTIV PUNIMESH

NR.	KODI	EMËRTIMI I PUNIMEVE.	NJËSIA	SASIA	ÇMIMI	VLEFTA
		1. PUNIME GERMIMI PER TRUPIN E RRUGES				0
1	3.98/b	Germim dheu me ekskavator zingjir, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	2008		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	2008		
		2. PUNIME SHITESASH PER RRUGEN				
7	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur me makineri	m2	5217		
8	3.212/b	Shtrese stabilizant t=10cm	m2	5217		
10	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	4586		
11	3.226/1	Shtrese asfaltbetoni me granil guri kave, 4cm, me makineri	m2	4586		

12	3.244/1	Struktura te holla monolite betoni C 20/25	m3	63.5		
		3. PUNIME PER KANALIN ANESOR				
3	3.98/a	Germim dheu me ekskavator zingjir 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	380		
4	3.158/5a	Transport dheu me auto deri 5.0 km	m3	380		
9	3.183/a	Shtrese zhavor lumi t=10cm	m2	645		
13	3.244/1	Struktura te holla monolite betoni C 20/25	m3	168		
14	2.182	F V konstruksione metalike te thjeshta	ton	2.52		
		3. PUNIME PER MURET MBAJTESE				
15	3.337	Gabiona me rrjete teli te zing, gure kave 2x2x1.5m	m3	378		
16	3.340	Gabiona me rrjete teli te zing, gure kave 1x2x1.5m	m3	27		
18	2.112	Mure buto betoni C 12/15	m3	45		
19	2.519	F.V. Tub kanalizimi pvc Ø 90	ml	10.5		
		4. PUNIME PER TOMBINO				

5	3.98/a	Germim dheu me ekskavator zingjir 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	6		
6	3.158/5a	Transport dheu me auto deri 5.0 km	m3	6		
17	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	6		
		4. PUNIME PER SINJALISTIKEN RRUGORE				
20	3.954	FV tabela rrugore treguese 60x20cm	copë	4		

Shuma Analiza	29,585,237.41
Fondi Rezervë (5.0%)	1,479,261.87
Shuma Analiza + Fondi Rezervë (5.0%)	31,064,499.28
Shuma TVSH (20%)	6,212,899.86
Totali	37,277,399.14