

Projektuesi: Bashkia Kucove

Objekti: Rikualifikim i rrugeve
"Ligate-Lumas-Dokollare-Pellumbas"

Datë: 01-10-2024

PREVENTIV

NR	KODI	EMËRTIMI I PUNIMEVE	NJËSIA	SASIA
		1. PUNIME GERMIMI		
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	410.0
		Shuma 1:		
		2. PUNIME DHEU		
2	2.37/3a	Transport materiale ndertimi, dheu me auto deri 3.0 km	m3	410.0
		Shuma 2:		
		3. PUNIME SHITRESASH		
3	3.212/b	Shtrese stabilizant t=10cm	m2	14198.0
4	3.207/1	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m2	14198.0
5	3.178	Ndertim kasonete ne toke te bute	m2	450.0
		Shuma 3:		
		4. ANALIZA TEKNIKE		
6	3.233/4	Shtrese asfaltbetoni me zall lavatrice, 7cm, me makineri	m2	12620.0
		Shuma 4:		
		5. PUNIME BETONI DHE B/A		
7	2.564	Themel butobetoni C20/25	m3	37.0
8	2.112	Mure buto betoni C 12/15	m3	50.0
		Shuma 5:		
		6. PUNIME BETONI E BETONARMEJE		
9	3.244	Struktura monolite betoni C 20/25	m3	14.0
		Shuma 6:		

7. PUNIME HEKUR BETONI				
10	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	1.0
11	2.166/1a	F V hekur betoni periodik Ø > 12 mm	ton	1.0
Shuma 7:				
8. PRODHIMI I MATERIALEVE TE NDERTIMIT				
12	1.131/p	Tuba betoni Ø 400 mm	m	38.0
Shuma 8:				
9. TE NDRYSHME, ELEKTRIKE DHE SINJALISTIKA				
13	3.922/1	F.v. Tabele drejtkëndore (tregimi)(AxB) e vogël 60x90	copë	8.0
14	3.169	F V shtylla metalike per ndriçim, H=7m, d=160mm	copë	20.0
15	3.168	FV krah shtylla metalike KRH - MSI 1500/1500/10	copë	20.0
16	3.175	FV ndricues Smart VP CL1 CR M-S 250W GG FAE 44004,me llampe 250W 230V	copë	20.0
17	3.176	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	copë	20.0
Shuma 9:				
10. PUNIME TE NDRYSHME				
18	3.652	Furnizim, vendosje tuba plastmasi ø 200	m	15.0
19	3.654/1	Furnizim, vendosje tuba plastmasi ø 80	m	400.0
Shuma 10:				
11. INSTALIME PER NDRICIM				
20	2.496	F.V. Elektroda tokezimi, profil zingato e bakerizuar , L=1.5m	copë	20.0
Shuma 11:				
12. GAZ E NAFTESJELLES				
21	4.131/3.5	F.V.ne toke kablllo Cu fuqie ÷1000V, me izolim gome e mbulesë plastmasi, te armuar, 4x10mm ²	m	400.0
Shuma 12:				
Shuma Analiza				

Fondi Rezervë (0.0%)	0.00
Shuma Analiza + Fondi Rezervë (0.0%)	44,553,956.00
TVSH (20%)	8,910,791.00
Shuma me TVSH	53,464,747.00
Totali	53,464,744.00

Preventivuesi:

Bashkia Kucove



Shënime:

