



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

OBJEKTI : Ndertim Blloku Paskuqan 1 " Hasan Tahsin+ Hasan Gerxhaliu+ Haxhi Isuf Banka+ Inajete Dumi+ Asim Aliko 1+Asim Aliko 2

OBJEKTI : Ndertim Rruga "Hasan Tahsin " Paskuqan 1 , Bashkia Kamez

L= 310 m , B=7m , Asphalt = 4.5 m , kunete 1x0.5 m , trotuare 2 x1 m

L= 310

A	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	167.4		
2	3.158/5a	Transport dheu me auto 5km	m ³	167.4		
3	An. 8	Mbushje me çakell shkembor	m ³	209.25		
4	3.211	Shtrese çakelli T=20cm	m ²	1395		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1395		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1395		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	1395		
8	2.207	Mur betoni C 16/20 + shkallet	m ³	161.20		
9	3.288	F.V Hekur betoni l zakonshem O > 10 mm	ton	4.03		
10	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Ø 1.0 m	cope	2		
11	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike p	m ³	2		
12	3.949/1	Vijeime me boje bikomponente 15cm(kembesore bardh e kuq)	cope	620		
13	3.934/1	Tabele sinjalistike 60cm		3		
SHUMA I						
II						
PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	155		
2	3.158/5a	Transport çakelli me auto 5km	m ³	155		
3	3 An. 8	Mbushje me çakell shkembor	m ³	77.5		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	304		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	15.26		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	10		
SHUMA II						
III						
PUNIME TROTUARE (2x1 m)						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	52.7		
2	3.158/5a	Transport dheu me auto 5km	m ³	52.7		
3	3 An. 8	Mbushje me çakell shkembor	m ³	79.05		
4	3.208	Shtrese çakelli T=10cm	m ²	527		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5 cm	m ²	527		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	620		
7	2/262/4	Beton per fiksime bordure C16/20	m ³	18.6		
8	2.109/2	Shtrese betoni trotuari	m ³	52.7		
9	3.961	F.V. Fidane Peme dekorative	cope	25		
SHUMA III						
IV						
PUNIME NE KUN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	248		
2	3.158/5a	Transport çakelli me auto 5km	m ³	248		
3	3.164/1b	Mbushje me çakell shkembor	m ³	124		
4	3.164/1t	F.V. Tuba I brinjezuar Ø 315	ml	304		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	6		
SHUMA IV						
V						
PUNIME PER NDRICIMIN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA

1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	310		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	310		
3	3.176	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	9		
4	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	1		
5	3.139	Germime dheu me ekskavator me goma	m³	46.5		
6	3.158/5a	Transport dheu me auto 5km	m³	46.5		
7	2.261	Mbushje me rere	m³	6.2		
8	3.164/1b	Mbushje me çakell shkembor	m³	40.3		
			SHUMAV			
			SHUMA A			

OBJEKTI : Ndertim Rruga "Hasan Gerxhaliu " Paskuqan 1 , Bashkia Kamez

L=390m , B=4 m , Asfalt =4m

L= 390

B	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m³	156		
2	3.158/5a	Transport dheu me auto 5km	m³	156		
3	An. 8	Mbushje me çakell shkembor	m³	187.2		
4	3.211	Shtrese çakelli T=20cm	m²	1560		
5	3.212/b	Shtrese stabilizanti t=10cm	m²	1560		
6	3.222/1	Shtrese binderi 1x5 cm	m²	1560		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m²	1560		
8	2.207	Mur betoni C 16/20 + shkallet	m³	44.00		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	1.10		
10	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	2		
11	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike p	m³	1		
12	.426/2	Prishje mur blloqe betoni	ml	200		
13	3.949/1	Vijeze me boje bikomponente 15cm(kembesore bardh e kuq)	cope	780		
	3.934/1	Tabele sinjalistike 60cm		3		
			SHUMA I			
IV						
PUNIME NE KUN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m³	156		
2	3.158/5a	Transport çakelli me auto 5km	m³	156		
3	3.164/1b	Mbushje me çakell shkembor	m³	78		
4	3.164/1t	F.V. Tuba I brinjezuar Ø 315	ml	384		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	8		
			SHUMA IV			
			SHUMA B			

OBJEKTI : Ndertim Rruga "Haxhi Isuf Banka " Paskuqan 1 , Bashkia Kamez

L=280 m , B= 4 m , Asfalt = 4 m ,

L= 280

C	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m³	112		
2	3.158/5a	Transport dheu me auto 5km	m³	112		
3	3.164/1b	Mbushje me çakell shkembor	m³	168		
4	3.211	Shtrese çakelli T=20cm	m²	1120		
5	3.212/b	Shtrese stabilizanti t=10cm	m²	1120		
6	3.222/1	Shtrese binderi 1x5 cm	m²	1120		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m²	1120		
8	2.207	Mur betoni C 16/20 + shkallet	m³	37.40		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	0.45		
10	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	4		
11	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike p	cope	2		
12	.426/2	Prishje mur blloqe betoni	m³	170		
13	3.949/1	Vijeze me boje bikomponente 15cm(kembesore bardh e kuq)	ml	560		
14	3.934/1	Tabele sinjalistike 60cm	cope	2		
			SHUMA I			
			SHUMA C			

OBJEKTI : Ndertim Rruga "Inajete Dumi " +Paskuqan 1 , Bashkia Kamez

D	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	112		
2	3.158/5a	Transport dheu me auto 5km	m ³	112		
3	3.164/1b	Mbushje me çakell shkembor	m ³	73.5		
4	3.211	Shtrese çakelli T=20cm	m ²	560		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	560		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	560		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	560		
8	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	2		
9	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike prej betoni perفشire linjat dhe aksesoret)	cope	1		
10	3.949/1	Vijezime me boje bikomponente 15cm(kembesore bardh e kuq)	ml	480		
11	3.934/1	Tabele sinjalistike 60cm	cope	2		
II						
PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	64		
2	3.158/5a	Transport çakelli me auto 5km	m ³	64		
3	3 An. 8	Mbushje me çakell shkembor	m ³	32		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	157		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	7.88		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	5		
SHUMA II						
III						
PUNIME NE KUN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	72		
2	3.158/5a	Transport çakelli me auto 5km	m ³	72		
3	3.164/1b	Mbushje me çakell shkembor	m ³	36		
4	3.164/1t	F.V. Tuba I brinjezuar Ø 315	ml	158		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	3		
SHUMA III						
SHUMA D						
OBJEKTI : Ndertim Rruga "Asim Aliko 1+Asim Aliko 2 " +Paskuqan 1 , Bashkia Kamez						

L=617 m , B= 5 m , Asfalt = 4.5 m , kunete 1x0.5 m ,

L= 617

E	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	555.3		
2	3.158/5a	Transport dheu me auto 5km	m ³	555.3		
3	An. 8	Mbushje me çakell shkembor	m ³	141.75		
4	3.211	Shtrese çakelli T=20cm	m ²	2776.5		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	2776.5		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	2776.5		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	2776.5		
8	2.207	Mur betoni C 16/20 + shkallet	m ³	231.38		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	5.78		
10	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	2		
11	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike p	cope	1		
12	.426/2	Prishje mur blloqe betoni	m ³	370.2		
13	3.949/1	Vijezime me boje bikomponente 15cm(kembesore bardh e kuq)	ml	1334		
14	3.934/1	Tabele sinjalistike 60cm	cope	1		
SHUMA I						
II						
PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	308.5		
2	3.158/5a	Transport çakelli me auto 5km	m ³	308.5		
3	3 An. 8	Mbushje me çakell shkembor	m ³	154.25		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	607		

5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	30.442		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	17		
		SHUMA II				
		SHUMA E				
		SHUMA A- E				
		TVSH 20%				
		TVSH TOTALE				

Shenim: Preventivi eshte hartuar ne baze te VKM nr.216, date 13.04.2023

PREVENTIVUES :
Ing. Hajredin Murgu



Drejtoresha Projekteve dhe Investimeve
Ing. Flora MUÇA




MIRATOJ
Rakip SULI

KRYETAR
