

PREVENTIV PUNIMESH

OBJEKTI: NGRITJA E QENDRES PER TRAJTIMIN E KAFSHEVE TE RRUGES

NR	Nr. Analizes	Pershkrimi i punimeve	Njesia	Sasia	Çmimi	Vlera
A. PUNIME NDERTIMI						
1. PUNIME DHEU						
1	2.19	Hedhje. Rrafshim, mbushje dheu me krah kategoria 3	m ³	50.0		
2	2.30	Germim themele e plinta b>2m, ekskavator me zhinxhir 0.5m3 shkarkim ne auto	m ³	150.0		
3	2.37/1b	Transport materiale ndertimi dheu me auto deri 6km	m ³	100.0		
		Shuma 1	Lek			
2. PUNIME BETON ARME						
1	2.258	Nenshtrese zhavori poshte shtreses niveluese te betonit nen themele (20 cm)	m ³	15.00		
2	2.262/5	Shtrese betoni C20/25	m ³	14.00		
3	114	Plinta e bazamente b/a monolite deri 20 m3 C - 16/20	m ³	34.00		
4	2.117/1b	Kollona b/a monolite C 25/30 h ~ 4m	m ³	4.25		
5	2.125/1	Soleta b/a monolite me tulla me 6 vrima, Hd = 6m, trashes	m ²	80.00		
6	2.262/4	Shtese betoni C16/20 , soleta	m ³	11		
7	2.119/1a	Trare e arkitrare b/a C20/25 h ~ 4m	m ³	16.00		
8	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	8.10		
9	2.166/1a	E/V hekur betoni periodik Ø > 12 mm	ton	6.20		
10	2.181	F V konstruksione metalike te perbera (ambjenti I hapur, kafazet, muri rrethues)	ton	12.00		
11	3.793	F.V. rrjete zingat, per kafazet	m ²	400.00		
12	3.721	F.V. Llamarine xingat e valezuar	m ²	192.00		
		Shuma 2	Lek			
3. PUNIME MURATURE						
1	2.71/2	Mur me tulla te lehtsuara dopio deri 8 m, LL.P. M-25	m ³	30		
2	2.86	Mur me tulla me 6 vrima, t=12cm h~3m, ll perz M 15	m ³	64		
		Shuma 3	Lek			
4. PUNIME ÇATIJE OSE TARACE						
1	2.239/a	Shtrese termoizoluese me polistirol t=10cm	m ²	129		
2	2.197	Hidroizolim me emulsion bitumi dhe 2 shtresa katrama	m ²	200		

3	2.219	Çati vendi e zakonshmeHD-8mmbuluar tjegull marsejeze	m2	129		
4	2.209	Ulluk shkarkimi vertikal llamarine cingat Ø 100 mm	ml	18.00		
5	2.212	Ulluk shkarkimi horizontal llamarine cingat 33 cm	ml	47.00		
		Shuma 4	Lek			
5. PUNIME SHITRESA DHE HIDROIZOLIMI						
1	2.264	Shtrese lluster çimento 1:2 20mm	m ²	78.0		
2	2.195	Hidroizolim me emulsion dhe 2 duar bitum	m ²	30.0		
3	2.267/a	Shtresë me pllaka grez porcelanat	m ²	78.0		
4	2.196/c	H/izolim me dy shtresa Mapei	m ²	30.0		
		Shuma 5	Lek			
6. PUNIME SUVATIMI DHE VESHJE						
1	2.303/1	Suva solete h > 4 m me drejtues, me pompe	m ²	78.0		
2	2.310/1	Suva brenda mur tulle h~4m me pompe, llaç perzier M 25	m ²	441.0		
3	2.331	Suva e zakonshme fasade mur tulle ~ 8m	m ²	109.0		
4	2.328	Patinim muri	m ²	519.0		
5	2.404/1	Boje hidroplastike importi cilesi e I-re (brenda)	m ²	519.0		
6	2.404/1	Boje hidroplastike importi cilesi e I-re (jashte)	m ²	109.0		
7	2.324a	Plintuse grez	ml	150.0		
		Shuma 6	Lek			
7. DYER DHE DRITARE						
1	2.386/2	V F dyer te blinduara importi.	m ²	4.00		
2	2.388/1	V F dyer te brendeshme tamburate te rimesuara	m ²	11.40		
3	2.395	Dyer d/alumini tek xh.	m ²	3.80		
4	2.375/1	F V dritare d/alumini plastike me dopio xham	m ²	13.00		
		Shuma 7	Lek			
8. PUNIME TE NDRYSHME						
1	2.273/1a	Shtrese me pllaka graniti t=3cm davancale dritare mermeri	m ²	13		
		Shuma 8	Lek			
		SHUMA A (1÷8)	Lek			
B. PUNIME ELEKTRIKE						
1	2.490/d	F.V Kasete plastike KE me 12 modular (vende)	cope	1		
2	2.490/f	F.V Kasete plastike KE me 36 modular (vende)	cope	1		
3	2.547	Panel I matjes se energjise 1/3 fazor, 10 poste	cope	1		
4	2. a-108	Automat magneto-termik 380V,25A, 4P	cope	2		

5	2.490/1	F.V Automat termo/el.manj. diferencial 2P 220V, 32A,	cope	2		
6	2,101	F.V. automat termo.manjetik diferencial 2p220v,20Adl=0,03A	cope	6		
7	2.490/1b	F.V Automat termo/el.manj. diferencial 2P 220V, 16A	cope	3		
8	2a.120	F.V. Llama sinjalizimi 220v 1,2w	cope	6		
9	4,155/4	F.V. kuti shperndarese PT7,PT8, PT11	cope	7		
10	2.481/1	F.V percjelles PV-500 Ø 1.5 mm2	ml	150		
11	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	ml	400		
12	2.481/3	F.V percjelles PV-500 Ø 4 mm2	ml	100		
13	2.481/5	F.V percjelles PV-500 Ø 10 mm2	ml	60		
14	2.481/4	F.V percjelles PV-500 Ø 6 mm2	ml	100		
15	4.131/3.7	F.V.ne toke kablllo Cu fuqie ±1000V, me izolim gome e mbulese plastmasi, te armuar, 4x25mm2	ml	50		
16	An.1	kabell interneti cad 6	ml	100		
17	2.a-93	F.V. Percjelles CU per tokezim d=25mm2 I zhveshur	ml	50		
18	480/5	Tub shllang Ø 32-36mm	ml	80		
19	480/1	Tub shllang Ø 14-17mm	ml	80		
20	2.480/3	Tub shllang Ø 22-26mm	ml	250		
21	2.483	Çelsa nje polar 10A 280V komplet	cope	10		
22	2.487/e	F.V kuti suport pllaket 2 modular	cope	22		
23	2.485/e	F.V priza shuko jashte murit 2P+T IP=54	cope	2		
24	2.485/d	Priza shuko universale Komplet	cope	16		
25	2.485/b	F.V priza bivalente 220V 10A 2P-T	cope	5		
26	2.483	Priza per internet komplet	cope	5		
27	An.2	Ndricues Katror LED me24w , 6000K,2400lm,	cope	17		
28	An.3	16 Port Rackmount Switch profesional	cope	1		
29	2a-139	FV ndricues evakuimi 1x11wIP40	cope	1		
30	An.4	FV Fiber Optike, 8 core, Multi Mode per instalim	ml	100		
		Shuma I				
		NDRICIMI I JASHEM				
1	An5	FV. Shtyllë ndricimi dekorative Cilindrike H = 7.8 m me dy diametra D1 114 dhe D2 76 e zinguar dhe e lyster me boje elektrostastatike me pjekje ne temp 400°C e kompletuar me morsete, kapak, sigures me spesor 2.5 - 3.5 mm. Shoqruar me nje ndricues dekorativ LED OSRAM ku duhet te jete jo me i vogel se 21000 lm, me ngjyre drite 4000K me lente polikarbonat asimetricke dhe guarnicion sillkoni. Ndricuesi duhet pa krah dhe i futur ne shtyll . Karkasa e ndricuesit duhet	copë	10		
2	3.172	F.V. Kuader komandimi komplet me automat dhe fotoelement	copë	1		
3	3.654/1	Furnizim, vendosje tuba plastmasi ø 80	ml	270		
4	An.6	F.V. Puseta elektrike 30*30	copë	11		
5	An.7	F.V.Kabell cu FROR 3x 2.5mm2 .	ml	350		
6	2.496	F.V. Elektroda tokezimi, profil zingato e bakerizuar , L=1.5m	copë	11		
7	2.262/4	Shtrese betoni C 16/20	m3	3		
8	4.141/a7.	F.V. shirit sinjalizimi per kablllo nen toke ne gjithë gjatesin e linjes se ndricimit.	ml	1500		
		Shuma II				
		TOKEZIMI				
1	An.8	Shirit tok hekuri zingato 30x3 mm , + zbritje	ml	60		
2	An.9	Maja rrufepritesezingato Dn-16mm,L0,5m	cope	13		
3	2.496	F.V. Elektroda tokezimi, profil zingato e bakerizuar , L=1.5m	copë	6		
4	3.176	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	6		
5	An.10	Fiksues te konturit ne parapet	cope	20		
6	An.11	Fiksues te shkarkueses ne fasade	cope	8		
		Shuma III				
		SHUMA B (I+II+III)	Lek			

C. PUNIME MEKANIKE						
1.PUNIME HVAC (NGROHJE-VENTILIM)						
1	Analize	F.V. Njesi e jashtme Multisplit mural 9.0 kW ne ftohje dhe 10 kW ne ngrohje.	cope	1.00		
2	Analize	F.V Njesi e brendshme Murale 1.3, 2.5 kW ne ftohje dhe 1.3, 2.8 kW ne ngrohje.	cope	5.00		
		Shuma 1	Lek			
2. PUNIME MN Z (MBROJTJA NGA ZJARRI)						
1	2.511	Hidrant Dn 80 PN16	cope	8.00		
		Shuma 2	Lek			
		SHUMA C (1÷2)	Lek			
D. PUNIME HIDRAULIKE						
1	2.492	F.V tub xingato dhe rakorderi Ø>1"	kg	9.00		
2	2.495	F.V lavaman porcelani importi me mishelator	cope	2.00		
3	2.501	F.V wc allafrenga importi	cope	2.00		
4	2.514	F.V pilete dyshemeje Ø40 mm	cope	2.00		
5	2.491/a	F.V tuba dhe rakorderi ujesjellesi PPR d=20 ~ 25mm, Pn 25	ml	20.00		
6	2.484	F.V Saraçineske PPR 3/4"	cope	2.00		
7	2.215	F.V bolier 80 liter, uje te ngrohte	cope	2.00		
8	2.516/1	F.V tuba e rakorderi PVC	kg	30.00		
9	2.512/3	F.V kolektor shperndares 3/4" (5+5)	cope	1.00		
10	An	F.V Pompe me pulmon 24 litra	cope	1.00		
11	2.596	F.V. pusete shkarkimi b/a 200x200cm, h=250cm, t=25cm	cope	1.00		
12	2.2013	F V rezervuari zingato 500 litra	cope	1.00		
13	2.425/2	Grope septike 12 m3 e parafabrikuar	cope	1.00		
		SHUMA D	Lek			
E. PUNIME SISTEMIMI						
1	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m ²	195		
2	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makine	m ²	195		
3	2.262/4	Shtese betoni C16/20	m ³	32		
4	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m ³	420.0		
5	3.158/5a	Transport dheu me auto deri ne 5 km	m ³	420.0		
6	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri per mbushje	m ³	250.0		
7	3.616	F V bordura betoni 12x25 cm	ml	125.0		
8	2.262/1	Shtrese betoni C 7/10 nen bordura	m ³	5.0		
9	3.643	Mbjellje bari ne skarpat	m ²	355.195		
10	An	F.V tuba PE SN8 Ø 250	ml	42		
11	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	2		
		Punime muri rrethues				
12	2.119/1a	Trare e arkitrare b/a C20/25 h ~ 4m	m ³	42.0		

13	2.182	F V konstruksione metalike te thjeshta	ton	0.44		
14	3.793	F.V. rrjete zingat	m2	200		
15	2.390/1	F.V dyer metalike te jashtme	m ²	4.00		
		SHUMA E	Lek			
		TOTAL A+B+C+D+E	Lek			
		T.V.SH 20%				
		SHUMA TOTALE				