

PREVENTIV

Objekti: Sistemim Asfaltim Rruqa Fshati Burim (Faza II, Prog. 0+600÷0+937)
Bashkia Dibër

Nr.	NR.AN	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	ÇMIMI	VLERA
1 PUNIME GERMIMI DHE MBUSHJE NE RRUGE						
1	3.104/b	Germim dheu me ekskavator 0.5 m ³ , b > 2 m, toke zak, kategoria IV, me shk ne mjet (prishje e shtreses egzistuese t=10 cm)	m ³	62,00		
2	An-9	Mbushje me zhavor ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	2,883		
3	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	62,00		
		Shuma 1				-
2 PUNIME ASFALTIMI						
1	An.164/1a	Shtresa me cakell e gur gurore, perhapur e ngjeshur me makineri 30 cm	m ³	124,00		
2	3.212/b	Shtrese stabilizant 10 cm	m ²	1.240,00		
3	3.212/b	Shtrese stabilizant 10 cm per bankine	m ²	155,00		
4	3.229/1	Shtrese binderi me zall lavatrice, 5cm, me makineri	m ²	1.085,00		
5	3.231/1	Shtrese asfaltbetoni me zall lavatrice, 3cm, me makineri	m ²	1.067,50		
		Shuma 2				
3 PUNIME NE SINJALISTIKE						
1	An129	Vijezim shirita gjatesor dhe anesor me gjeresi 15 cm. Akrelike	ml	-		
2	An139	Vijezim shirita me gjeresi 30 cm, kalim kembesoresh. Akrelike	ml	-		
3	An158	FV tabela te ndryshme rrugore D=60cm	cope	-		
4	An157	F V tabela rrugore treguese 60x20cm	cope	-		
		SHUMA 3				
		SHUMA (1-3)				
		T.V.SH.	20%			
		SHUMA ME T.V.SH.				

Preventivues :
ERALD-G SH.P.K

Ing. Gezim Islami