

**PREVENTIV**

**Objekti: " Sistemim asfaltim rruga e fshatit Shumbate ", Bashkia Diber**

Nr	Nr AN	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
	<b>I</b>	<b>PUNIME NE RRUGE</b>				
1	3.89/a	Germim dheu me ekskavator 0.25 m <sup>3</sup> , toke zak, kategoria III, me shk ne mjet	m3	1,123	-	-
3	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	1,100	-	-
4	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m <sup>2</sup>	3,619	-	-
5	3.212/b	Shtrese stabilizanti 10cm per rrugen	m <sup>2</sup>	3,619	-	-
6	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m <sup>2</sup>	3,619	-	-
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m <sup>2</sup>	3,619	-	-
8	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri ( per bamkinen)	m <sup>3</sup>	279	-	-
9	3.212/b	Shtrese stabilizanti 10cm per bankinen	m <sup>2</sup>	900	-	-
		<b>Shuma I</b>			-	-
	<b>II</b>	<b>PUNIME KANALI</b>			-	-
1	3.89/a	Germim dheu me ekskavator 0.25 m <sup>3</sup> , toke zak, kategoria III, me shk ne mjet	m3	305	-	-
2	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	305	-	-
		<b>Shuma II</b>			-	-
	<b>III</b>	<b>PUNIME TOMBINO D-600</b>			-	-
1	2.258	Nenshtrese zhavori	m3	0.15	-	-
2	3.243/1	Struktura te holla monolite betoni C 16/20	m3	1	-	-
3	3.164/4t	F V tuba te brinjezuar HDPE SN8 d=600 mm	ml	6	-	-
		<b>Shuma III</b>			-	-
		<b>SHUMA</b>			-	-
		<b>FONDI REZERVE 3%</b>			-	-
		<b>SHUMA</b>			-	-
		<b>TVSH 20 %</b>			-	-
		<b>TOTALI</b>			-	-

**PREVENTIVOI  
"Novatech Studio"shpk  
Ing.Emil Nova**