



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

OBJEKTI : Ndertim Blloku Paskuqan 1 Koder " Ltot=1164 ml

OBJEKTI : Ndertim Rruga "Seg Lidhja e Prizrenit " Paskuqan 1 Koder , Bashkia Kamez

L= 174 m , B= 7 m , Asphalt = 4.5 m , kunete 1x0.5 m , trotuare 2 x1 m

L= 174

A	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	78.3		
2	3.158/5a	Transport dheu me auto 5km	m ³	78.3		
3	3.164/1b	Mbushje me çakell shkembor	m ³	93.99		
4	3.211	Shtrese çakelli T=20cm	m ²	783		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	783		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	783		
7	3.224/1	Shtrese asfaltobetoni 1x3cm	m ²	783		
8	2.207	Mur betoni C 16/20	m ³	52.96		
9	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	1.32		
10	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike p	cope	2		
11	.426/2	Prishje mur blloqe betoni	m ³	52.2		
12	3.949/1	Vijezime me boje bikomponente 15cm(kembesore bardh e kuq)	ml	348		
13	3.934/1	Tabele sinjalistike 60cm	cope	2		
SHUMA I						
II						
PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	69.6		
2	3.158/5a	Transport çakelli me auto 5km	m ³	69.6		
3	3.164/1b	Mbushje me çakell shkembor	m ³	34.8		
4	3.164/1t	F.V. Tuba I brinjezuar Ø 315	ml	170		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	8.56		
6	2.342	Puseta shiu me zgare 40x60 + kapak gize	cope	6		
SHUMA II						
III						
PUNIME TROTUARE(2x1 m)						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	29.58		
2	3.158/5a	Transport dheu me auto 5km	m ³	29.58		
3	3.164/1b	Mbushje me çakell shkembor	m ³	35.50		
4	3.208	Shtrese çakelli T=10cm	m ²	295.8		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5 cm	m ²	295.8		
6	3.616/a	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	348		
7	2/262/4	Beton per fiksime bordure C16/20	m ³	10.44		
8	3.241	Shtrese betoni trotuari	m ³	29.58		
SHUMA III						
IV						
PUNIME NE KUN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	69.6		
2	3.158/5a	Transport çakelli me auto 5km	m ³	69.6		
3	3.164/1b	Mbushje me çakell shkembor	m ³	34.8		
4	3.164/1t	F.V. Tuba I brinjezuar Ø 315	ml	170		
5	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	5		
SHUMA IV						
V						
PUNIME PER NDRICIMIN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	174		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndrçimin	ml	174		

3	3.176	F.V. pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	5	
4	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	1	
5	3.139	Germime dheu me ekskavator me goma	m ³	26.1	
6	3.158/5a	Transport dheu me auto 5km	m ³	26.1	
7	2.261	Mbushje me rere	m ³	3.48	
8	3.164/1b	Mbushje me çakell shkembor	m ³	22.62	
SHUMAV					
SHUMA A					

OBJEKTI : Ndertim Rruga "Lasgush Poradeci +seg. " Paskuqan I Koder , Bashkia Kamez

L1= 207m , B= 7 m , Asphalt = 4.5 m , kunete 1x0.5 m , trotuare 2 x1 m ,L2=105, B=4m L= 312

B	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	140.4		
2	3.158/5a	Transport dheu me auto 5km	m ³	140.4		
3	An. 8	Mbushje me çakell shkembor	m ³	202.73		
4	3.211	Shtrese çakelli T=20cm	m ²	1351.5		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1351.5		
6	3.222/2	Shtrese binderi 1x5 cm	m ²	1351.5		
7	3.226/1	Shtrese asfaltbetoni 1x3cm	m ²	1351.5		
8	2.207	Mur betoni C 16/20 + shkallet	m ³	45.54		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	1.14		
10	3.581	Mbringritje h=0.5 m, Pusete ekzistuese UZ Ø 1.0 m	cope	5		
11	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike p	cope	5		
12	.426/2	Prishje mur blloqe betoni	m ³	93.6		
13	3.949/1	Vijezime me boje bikomponente 15cm(kembesore bardh e kuq)	ml	724		
14	3.934/1	Tabele sinjalistike 60cm	cope	3		
SHUMA I						
II PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	82.8		
2	3.158/5a	Transport çakelli me auto 5km	m ³	82.8		
3	3 An. 8	Mbushje me çakell shkembor	m ³	41.4		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	203		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	10.18		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	7		
SHUMA II						
III PUNIME TROTUARE(2x1 m)						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	18.63		
2	3.158/5a	Transport dheu me auto 5km	m ³	18.63		
3	3.164/1b	Mbushje me çakell shkembor	m ³	26.39		
4	3.208	Shtrese çakelli T=10cm	m ²	351.9		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5 cm	m ²	351.9		
6	3.616/a	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	414		
7	2/262/4	Beton per fksim bordure C16/20	m ³	12.42		
8	3.241	Shtrese betoni trotuari	m ³	35.19		
SHUMA III						
IV PUNIME NE KUN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	82.8		
2	3.158/5a	Transport çakelli me auto 5km	m ³	82.8		
3	3 An. 8	Mbushje me çakell shkembor	m ³	41.4		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	203		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	5		
SHUMA IV						
V PUNIME PER NDRICIMIN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	207		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndrçimin	ml	207		
3	3.176	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	7		

4	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	1	
5	3.139	Germime dheu me ekskavator me goma	m ³	31.05	
6	3.158/5a	Transport dheu me auto 5km	m ³	31.05	
7	2.261	Mbushje me rere	m ³	4.14	
8	3.164/1b	Mbushje me çakell shkembor	m ³	26.91	
			SHUMA V		
			SHUMA B		

OBJEKTI : Ndertim Rruga "Laze Shantoja " Paskuqan 1 Koder , Bashkia Kamez

L=168 m , Asphalt = 4m

L= 168

C	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I	PUNIME NE RRUGE					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	67.2		
2	3.158/5a	Transport dheu me auto 5km	m ³	67.2		
3	An. 8	Mbushje me çakell shkembor	m ³	100.8		
4	3.211	Shtrese çakelli T=20cm	m ²	672		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	672		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	672		
7	3.224/1	Shtrese asfaltbetoni 1x3cm	m ²	672		
8	2.207	Mur betoni C 16/20 + shkallet	m ³	16.8		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	0.42		
10	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike p	cope	2		
11	.426/2	Prishje mur blloqe betoni	m ³	67.2		
12	3.949/1	Vijezime me boje bikomponente 15cm(kembesore bardh e kuq)	ml	436		
13	3.934/1	Tabele sinjalistike 60cm	cope	3		
			SHUMA I			
II	PUNIME NE KUN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	67.2		
2	3.158/5a	Transport çakelli me auto 5km	m ³	67.2		
3	3 An. 8	Mbushje me çakell shkembor	m ³	33.6		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	165		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	4		
			SHUMA II			
			SHUMA C			0.0

OBJEKTI : Ndertim Rruga "Lefter Talo " + " Rruga Lek Sidromi Paskuqan 1 Koder , Bashkia Kamez

L1=350 m , B= 6 m , Asphalt = 4.5 m , kunete 1x0.5 m , + Trotuar 1x1; L2=160,b=4m

L= 510

D	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I	PUNIME NE RRUGE					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	229.5		
2	3.158/5a	Transport dheu me auto 5km	m ³	229.5		
3	An. 8	Mbushje me çakell shkembor	m ³	221.5		
4	3.211	Shtrese çakelli T=20cm	m ²	2975		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	2975		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	2975		
7	3.224/1	Shtrese asfaltbetoni 1x3cm	m ²	2975		
8	2.207	Mur betoni C 16/20 + shkallet	m ³	112.20		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	2.81		
10	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Ø 1.0 m	cope	5		
11	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike p	cope	3		
12	.426/2	Prishje mur blloqe betoni	m ³	306		
13	3.949/1	Vijezime me boje bikomponente 15cm(kembesore bardh e kuq)	ml	1020		
14	3.934/1	Tabele sinjalistike 60cm	cope	6		
			SHUMA I			
II	PUNIME NE KUB					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	140		
2	3.158/5a	Transport çakelli me auto 5km	m ³	140		
3	3 An. 8	Mbushje me çakell shkembor	m ³	70		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	343		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	17.21		

6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	12		
			SHUMA II			
III	PUNIME NE KUN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	204		
2	3.158/5a	Transport çakelli me auto 5km	m ³	204		
3	3 An. 8	Mbushje me çakell shkembor	m ³	102		
4	3.an/1t	F.V. Tuba i brinjzuar Ø 315	ml	503		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	9		
			SHUMA III			
IV	PUNIME TROTUARE (1x1 m)					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	65.025		
2	3.158/5a	Transport dheu me auto 5km	m ³	65.025		
3	3.164/1b	Mbushje me çakell shkembor	m ³	86.7		
4	3.208	Shtrese çakelli T=10cm	m ²	433.5		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5 cm	m ²	433.5		
6	3.616/a	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	1020		
7	2/262/4	Beton per fiksime bordure C16/20	m ³	30.6		
8	3.241	Shtrese betoni trotuari	m ³	43.35		
			SHUMA IV			
V	PUNIME PER NDRICIMIN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	350		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	350		
3	3.176	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	10		
4	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	1		
5	3.139	Germime dheu me ekskavator me goma	m ³	52.5		
6	3.158/5a	Transport dheu me auto 5km	m ³	52.5		
7	2.261	Mbushje me rere	m ³	7		
8	3.164/1b	Mbushje me çakell shkembor	m ³	45.5		
			SHUMA V			
			SHUMA D			
			SHUMA A-D			
			TVSH 20%			
			TVSH TOTALE			

Shenim: Preventivi eshte hartuar ne baze te VKM nr.216, date 13.04.2023

Preventivues:

Ing. Eglantina Disha



Drejtori P.I-se

Ing. Flora MUÇA



MIRATOI

Rakip SULLI

KRYETAR

