

**MIRATOI
BASHKIA KLOS
Zj. VALBONA KOLA
KRYETARE**

PREVENTIV I PUNIMEVE						
EMRI I PROJEKTIT: "NDERTIM BAZAMENTE + SHPATULLA URA E FSHATIT FSHAT, KLOS (URE BELI)"						
Nr.	An. No.	Pershkrimi i zerit	Njesi	Sasia	Çmimi	Shuma
KATEGORIA 1: PUNIME DHERASH DHE PRISHJE						
2	3.110/b	Germim dheu me ekskavator zingjir, 1.0 m ³ , toke zak, kategoria IV, me shk ne mjet	m ³	69.00		
3	3.128/b	Germim shkambi i coptuar me ekskavator 1.0 m ³ , shkemb, ne themele gjeresi >2 m, me shkarkim ne mjet	m ³	46.00		
4	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	128.00		
5	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	115.00		
SHUMA 1						
KATEGORIA 2 : PUNIME BETONI						
Bazamente+Shpatulla Ure						
1	3.396/1	Mbushje me zhavorr (nenshtrese)	m ³	100.00		
2	3.240	Struktura monolite betoni C 12/15, per nenshtrese	m ³	4.76		
3	3.245	Struktura monolite betoni C 25/30, per themel	m ³	71.40		
4	3.245	Struktura monolite betoni C 25/30, per ballnat	m ³	36.25		
5	3.245	Struktura monolite betonarme C 25/30, per jastek	m ³	3.64		
6	3.245	Struktura monolite betoni C 25/30, per shpatullat	m ³	30.63		
7	3.289	F V hekur betoni Ç-5 Ø > 12mm	ton	0.55		
8	3.624	H / Izolim me emulsion, 2 duar bitum	m ²	47.60		
SHUMA 2						
SHUMA 1+2						
		Fond Rezerve 5%	5%			
SHUMA PA TVSH						
		T V S H 20%	20%			
SHUMA TOTALE						

Hartoi
"ERALD-G" sh.p.k

Perfaqeues
Ing. Gezim Islami