

Me projektin nr. 5944/3 prot.
14.10.2024


Seriali: 199F92A1-C64D-42FD-AEF5-A37815D5DFA2

Projektuesi: Mesude AHMETAJ
Objekti: "RRUGE AKSESI QEPARO FUSHE, NR. 1 DHE 2"

Data: 10-10-2024

PREVENTIV PUNIMESH

NR.	KODI	EMËRTIMI I PUNIMEVE.	NJËSIA	SASIA	ÇMIMI PA TVSH	VLEFTA PA TVSH
1. PUNIME SHPYLLEZIMI						
1	3.3	Preje e sistemit pemesh ø 10 ~ 20 cm	copë	9	0.00	0.00
SHUMA 1:						0.00
2. PUNIME GERMIMI						
2	3.104/b	Germim dhe me ekskavator zingjir, 0.5 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne mjet	m3	1125	0.00	0.00
3	3.158/5a	Transport dhe me auto deri 5.0 km	m3	1125	0.00	0.00
4	3.44/1	Germim kanalesh ne toke te bute, me krahe, me seksion deri 0.75 m ²	m3	90.69	0.00	0.00
SHUMA 2:						0.00
3. PUNIME SHITRESASH						
5	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri	m2	2250	0.00	0.00
6	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri	m2	2250	0.00	0.00
7	3.212/b	Shtrese stabilizant t=10cm	m2	2250	0.00	0.00
8	3.711	Shtrese Stabilizanti 8 cm	m2	250	0.00	0.00
SHUMA 3:						0.00
4. PUNIME ASFALTIMI						
9	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	1750	0.00	0.00
SHUMA 4:						0.00
5. ANALIZA TEKNIKE						
10	3.224/1	Shtrese asfaltbetoni me granil guri kave, 3cm, me makineri	m2	1750	0.00	0.00
SHUMA 5:						0.00
6. PRODHIMI I MATERIALEVE TE NDERTIMIT						
11	1.126/p	Bordura betoni 15x35cm	m	500	0.00	0.00
SHUMA 6:						0.00
7. PUNIME SHITRESASH 2						
12	2.262/4	Shtrese betoni C 16/20	m3	17.5	0.00	0.00
13	2.262/4	Shtrese betoni C 16/20	m3	21.25	0.00	0.00
14	2.261	Shtrese rere	m3	30.32	0.00	0.00
15	2.262/3	Shtrese betoni C 12/15	m3	2.88	0.00	0.00
SHUMA 7:						0.00
B. TE NDRYSHME, ELEKTRIKE DHE SINJALISTIKA						
16	3.164/1t	F V tuba te brinjeuar HDPE SN8 d=315 mm	ml	500	0.00	0.00
17	3.933/1	F.v. Tabela tetekendore normal me A-B, 90-30	copë	1	0.00	0.00
18	3.169	F V shtylla metalike per ndrçim, H=7m, d=160mm	copë	18	0.00	0.00
19	3.168	FV krah shtylla metalike KRH - MSI 1500/1500/10	copë	18	0.00	0.00
20	3.182	FV elektroda tokezimi te xinguara 50x3mm L=150cm	copë	18	0.00	0.00
21	3.176	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	copë	18	0.00	0.00
22	3.172	F V kuader komandimi komplet me santeri+fotoelement	copë	1	0.00	0.00
SHUMA 8:						0.00
9. UJESJELLES E KANALIZIM I JASHEM						
23	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	copë	20	0.00	0.00
SHUMA 9:						0.00
10. B. SINJALET HORIZONTALE						
24	3.942	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm. Bikoponente (sprajt)	ml	1000	0.00	0.00
SHUMA 10:						0.00
11. D. SINJALET DHE PAJISJET SHITESH, NGADALESUESIT E SHPEJTESISE						
25	3.955	FV tabela te ndryshme rrugore D=60cm	copë	2	0.00	0.00
SHUMA 11:						0.00
12. GAZ E NAFTESJELLES						
26	4.131/3.5	F.V ne toke kablo Cu fuqie +1000V, me izolim gome mbuleshe plastmasi, te armuar, 4x10mm2	m	300	0.00	0.00
SHUMA 12:						0.00



13. ANALIZA JASHTE LISTE							
27	AnAn 1	F.V Ndricues rruge LED, 100W, 5000K, IP65	copë	18	0.00	0.00	
28	An2	F.V Tub fleksibel me dy shtresa d=90mm	ml	510	0.00	0.00	
29	An3	F.V. Kabell 0.6/1 KV; tip RG7R; 5x10mm2	ml	200	0.00	0.00	
30	An+ 2.523	Tub pvc ø 200 (inkastrimin e shtyllës)	ml	14.4	0.00	0.00	
Shuma Analiza						SHUMA 13:	0.00
Fondi Rezervë (0.0%)							0.00
Shuma Analiza + Fondi Rezervë (0.0%)							0.00
Shuma TVSH (20%)							0.00
Shuma me TVSH							0.00
Totali							0.00

Preventivuesi: Mesude AHMETAJ



Investitori: Bashkia Himare

