



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

OBJEKTI: Rikonstruksion Rruga "Nene Tereza" Laknas

(L =1700 ml, B =14m, basf= 6m, 2x0.5 kunete, 2x2 trotuar)

An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera	
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.969	Skarifikim shtrese asfalti ekzistues me makineri	m ²	10200		
2	3.2	Prerje bime te vogla ø ~ 10cm	m ²	305		
3	2.426/3	Prishje shtresa betoni	m ³	100		
4	3.211	Shtrese çakelli T=20cm	m ²	100		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	100		
6	3.222/1	Shtrese binderi 1x5 cm	m ²	100		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	10200		
8	2,111	Mure betoni C12/15(themel,xokol betoni)	m ³	619.63		
9	3.288	F.V Hekur betoni I zakonshem O > 12 mm	ton	9.69		
10	3.558	elektrike prej betoni perfshire linjat dhe aksesoret)	cope	13		
11	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m +pastrim e llumrave me makineri+transport	cope	34		
12	2.426/2	Prishje mure me blloqe + transport	m ³	560		
13	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor).Termoplastike (paste) anesoret + aksi+vije zime kembesoret	ml	4250		
14	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	30		
15	An3.966.	Shkulje+mbjellje pemesh ekzistuese	cope	13		
16	3.643	Mbjellje bari	m ²	100		
17	3.643/a	F.V. Dhe' vegjetal per mbushje (brezat e gjelber)	m ³	57		
18	An3.164/6t.	Vendosje tuba te brinjezuar HDPE d=600 mm-1500mm	ml	170.0		
SHUMA I						
II PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	1360		
2	3.158/5a	Transport dheu me auto 5km	m ³	1360		
3	3.396	Mbushje me cakell pas mureve	m ³	1030		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	3332		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	170		
6	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	113		
SHUMA II						
III PUNIME TROTUARE(2x2m dy ane) 4480						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	280		
2	3.158/5a	Transport dheu me auto 5km	m ³	280		
3	3.164/1b	Mbushje me çakell shkembor	m ³	364		

4	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	4480		
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	4480		
6	3.616/9	FV Bordura betoni 15x25 cm	ml	2800		
7	2.262/4	Beton per fiksime bordure C16/20	m ³	84		
8	2.262/4	pllaka trotuari	m ²	4480		
SHUMA III						
IV	PUNIME NE KUZ(L=1700ml)					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.139	Germim dheu me eskavator	m ³	6715		
2	3.158/5a	Transport dheu me auto 5km	m ³	6715		
3	3.396	Mbushje me cakell pas mureve	m ³	2800		
5	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm (perfshire reren per mbrojtjen e tubit)	ml	0		
6	2.599	F.V. pusete shkarkimi 100x100, h=150, me kapak gize	cope	68		
SHUMA IV						
V	PUNIME PER NDRICIMIN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	3400		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndricimin	ml	3400		
3	3.17	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	136		
4	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	8		
5	3.139	Germime dheu me ekskavator me goma	m ³	255		
6	3.158/5a	Transport dheu me auto 5km	m ³	255		
7	2.261	Mbushje me rere	m ³	136		
8	3.353	Mbushje me shkemb te germuar me pare	m ³	119		
SHUMA IV						
VI	PUNIME PER GJELBERIMIN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
1	3.619/a	FV Bordura betoni 6x20 cm	ml	595		
SHUMA V						
TOTALI						
TVSH 20%						
TVSH TOTALE						

Shenim: Preventivi eshte hartuar ne baze te VKM nr.216, date 13.04.2023

Preventivues:

Ing. Eglantina Disha



Drejtori P.I-se

Ing. Flora MUÇA



**MIRATOI
Rakip SULI**

