



**REPUBLIKA E SHQIPERISE**  
**BASHKIA KAMEZ**  
**PREVENTIV**

**OBJEKTI : Ndertim Rruga "Pjeshkore Velipoje + rrugicat" Valias + Sistemim Asfaltim i Rruges "Ballshi  
"Valias + Rruga "Pingul me Hekuran Deden" Laknas**

**OBJEKTI : Ndertim Rruga "Pjeshkore Velipoje + rrugicat" Valias**

**( L<sub>Tot</sub> =170+325+210 ml=705ml, B =7m, basf= 4.2m 0.4kunete dy ane, trotuar 1m dy anet)**

A	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
<b>I</b>	<b>PUNIME NE RRUGE - L1</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	296.1		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	296.1		
3	3.164/1b	Mbushje me çakell shkembor	m <sup>3</sup>	296.1		
4	3.211	Shtrese çakelli T=20cm	m <sup>2</sup>	2961		
5	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	2961		
6	3.222/1	Shtrese binderi 1x5 cm	m <sup>2</sup>	2961		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri + 3 rampa per ngadalesim	m <sup>2</sup>	2961		
8	2,111	Mure betoni C12/15(themel,xokol betoni)	m <sup>3</sup>	128		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	9.6		
10	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike prej betoni perfshire linjat dhe aksesoret)	cope	4		
11	2.426/2	Prishje mur blloqe betoni	m <sup>3</sup>	320		
12	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor ).Termoplastike (paste ) anesoret + aksi+vije zime kembesoret	ml	1450		
13	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	6		
		<b>SHUMA I</b>				
<b>II</b>	<b>PUNIME NE KUB</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	338.4		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	338.4		
3	3.396	Mbushje me cakell pas mureve	m <sup>3</sup>	191		
4	3.164/1t	F.V. tuba te Brinjezuar SN-8 d=315 mm ( perfshire reren per mbrojtjen e tubit )	ml	1020		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m <sup>3</sup>	45.1		
6	2.342	Pusetet shiu 40 x 60, h = 100 cm, me kapak gize	cope	47		
		<b>SHUMA II</b>				
<b>III</b>	<b>PUNIME TROTUAR DY ANET( 1 x1 m)</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	112.8		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	112.8		
3	3.164/1b	Mbushje me çakell shkembor	m <sup>3</sup>	112.8		
4	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m <sup>2</sup>	1128		
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m <sup>2</sup>	1128		
6	3.616/9	FV Bordura betoni 15x25 cm	ml	1410		
7	2.262/4	Beton per fiksime bordure C16/20	m <sup>3</sup>	42.3		
8	2.262/4	Shtrese betoni C16/20 (trotuari)	m <sup>3</sup>	141		
		<b>SHUMA III</b>				
<b>IV</b>	<b>PUNIME PER NDRICIMIN</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>

2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	1410		
3	3.17	F V pusete elektrike kontrolli PVC 40x40x40cm	cope	23		
4	3.139	Germim dheu me eskavator	m <sup>3</sup>	493.5		
5	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	493.5		
6	2.261	Mbushje me rere	m <sup>3</sup>	211.5		
7	3.353	Mbushje me shkemb te germuar me pare	m <sup>3</sup>	282		
<b>SHUMA IV</b>						
<b>V</b>	<b>PUNIME PER GJELBERIMIN</b>					
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.619/a	FV Bordura betoni 6x20 cm	ml	82		
<b>SHUMA V</b>						
<b>SHUMA I-IV</b>						

**OBJEKTI : Sistemim Asfaltim i Rruges "Ballshi "Valias , Ltot= 610 ml**

**( L = 610 ml, B =9m, basf= 5m, bankine 2x1 + kanal I mbuluar 4 m )**

<b>B</b>	<b>An.</b>	<b>Emertimi i Punimeve</b>	<b>Njesia</b>	<b>Sasia</b>	<b>Cmimi</b>	<b>Vlera</b>
<b>I</b>						
<b>PUNIME NE RRUGE</b>						
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	854		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	854		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m <sup>3</sup>	915		
4	3.211	Shtrese çakelli T=20cm	m <sup>2</sup>	3050		
5	3.212/b	Shtrese stabilizanti t=10cm	m <sup>2</sup>	3050		
6	3.222/1	Shtrese binderi 1x5 cm	m <sup>2</sup>	3050		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m <sup>2</sup>	3050		
8	3.558	Spostim shtylle elektrike (Cmontim dhe montim shtylle elektrike prej betoni perfshire linjat dhe aksesoret)	cope	5		
9	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m	cope	2		
10	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor ).Termoplastike (paste ) anesoret + aksi+vije zime kembesoret	ml	1220		
11	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	4		
<b>SHUMA A</b>						
<b>II</b>	<b>PUNIME NE KUZ</b>					
<b>I</b>	<b>PUNIME K.U.Z. AksiRruges Ballshi DN 315,&amp; 600</b>					
1	2.426/5	Prishje mure betoni	m3	12		
2	3.405/1	Prishje struktura prej betoni (soletat ekzistuese ne rruget e intersektimit)	m3	38		
3	2.88	Mur me blloqe betoni 20cm, deri - 3m, me LL.P. M-15	m3	12		
4	3.139	Germim dheu me eskavator	m3	3,000		
5	3.47/1b	Mbushje, rafshim,ngjeshje me tokmak elektrik, cdo 30 cm, toke zak (mbushje me material të selektuar nga gërmimi për tubat e betonit KUZ)	m3	1,350		
6	3.158/5a	Transport dheu me auto deri 5.0 km	m3	1,650		
7	3.164/1t	F.V. tuba te brinjezuar HDPE SN8 d=315 mm	ml	168		
10	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	600		
11	2.575	Puse kontrolli 1x1x1.5m	cope	13		
<b>SHUMA B</b>						
<b>SHUMA B</b>						

**OBJEKTI : Ndertim Rruga "Pingul me Hekuran Deden" Laknas , Bashkia Kamez L=300 m; B=4 m , Basfalt = 4 m**

<b>C</b>	<b>An.</b>	<b>Emertimi i Punimeve</b>	<b>Njesia</b>	<b>Sasia</b>	<b>Cmimi</b>	<b>Vlera</b>
<b>L= 300</b>						
<b>I</b>						
<b>PUNIME NE RRUGE</b>						
<b>NR.</b>	<b>Nr.An</b>	<b>PERSHKRIMI I PUNIMEVE</b>	<b>NJESIA</b>	<b>SASIA</b>	<b>CMIMI</b>	<b>VLERA</b>
1	3.139	Germim dheu me eskavator	m <sup>3</sup>	180.0		
2	3.158/5a	Transport dheu me auto 5km	m <sup>3</sup>	180.0		
3	3.164/1b	Mbushje me çakell shkembor+bankine	m <sup>3</sup>	93.0		
4	3.211	Shtrese çakelli T=20cm	m <sup>2</sup>	1200		

6	3.222/1	Shtrese binderi 1x5 cm	m <sup>2</sup>	1200		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm	m <sup>2</sup>	1200		
8	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ $\Phi$ 1.0 m	cope	2		
9	3.949/1	Vizime me boje bikomponente 15cm(shirita gjatesor dhe anesor ).Termoplastike (paste ) anesoret + aksi+vije zime kembesoret	ml	680		
10	3.934/1	F.v. Tabele rrethi "detyrim" normal me D = 60	cope	4		
		<b>SHUMA I</b>				
		<b>SHUMA A-C</b>				
		<b>TVSH 20%</b>				
		<b>TVSH TOTALE</b>				

**SHENIM:** Preventivi eshte hartuar ne baze te VKM nr.216, date 13.04.2023

**Preventivues :**

**Ing. Eglantina DISHA**

**Drejtori P.I-se**

**Ing. Flora MUÇA**

**MIRATOI  
Rakip SULI**

**KRYETAR**

