



**MIRATOI
KRYETARI
TONIN MARINAJ**

PREVENTIV PUNIMESH

Objekti: "Sistemim Asfaltim rruget Zekaj - Zenelaj Koplik Siperm"

NR.	KODI	EMËRTIMI I PUNIMEVE.	NJËSIA	SASIA	ÇMIMI PA TVSH	VLEFTA PA TVSH
		1. PUNIME SHITESASH				
1	3.969	Skarifikim shtrese asfalti ekzistues me makineri	m2	2510	0.00	0.00
2	3.205/2	Shtrese zhavori lumi t=20cm, perhapur e ngjeshur me makineri	m2	1032	0.00	0.00
3	3.212/b	Shtrese stabilizant t=10cm	m2	3373	0.00	0.00
4	3.212/a	Shtrese stabilizanti t=5cm	m2	992	0.00	0.00
		SHUMA 1:				0.00
		2. PUNIME DHEU				
5	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	551	0.00	0.00
		SHUMA 2:				0.00
		3. ANALIZA TEKNIKE				
6	3.222/2	Shtrese binderi me granil gur kave, 6cm, me makineri	m2	2340	0.00	0.00
		SHUMA 3:				0.00
		4. PUNIME GERMIMI				
7	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjerësi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	310	0.00	0.00
		SHUMA 4:				0.00
Shuma Analiza						0
Fondi Rezervë (0.0%)						0.00
Shuma Analiza + Fondi Rezervë (0.0%)						0
Shuma TVSH (20%)						0
Shuma me TVSH						0

Preventivuesi:
"Novatech Studio"shpk
Ing.Emil Nova

Investitori Bashkia Malesi e Madhe