

PREVENTIVI PA CMIME

OBJEKTI: RIKONSTRUKSIONI I GODINES SE BASHKISE MEMALIAJ
BASHKIA MEMALIAJ

NR	NR/AN	EMERTIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
A	PUNIME DHEU DHE PRISHJE					
1	An.1	Prishja hidroizolim tarraca ekzistuese	m ²	300		
2	An.2	Heqje dyer ekzistuese	m ²	11.34		
3	An.3	Prishje suvatim muri + tavani	m ²	2076.4		
4	2.37/5a	Transport mbeturina 5 km	m ³	50		
5	An.4	Prishje pllaka ekzistuese	m ²	500		
SHUMA A						
B	PUNIME MURATURE					
3	2.66/2	Mure tulle t=12 cm	m ³	4.0		
SHUMA B						
C	PUNIME SHITRESASH					
1	2.262/1	Shtrese betoni C 16/20	m ³	20		
2	2.195	Hidroizolim me dy duar bitum (dyschemeja)	m ²	500		
3	2.267/b	Shtrese pllaka gres importi (60x60 cm)	m ²	500		
4	2.324a	Plintuse pllaka gres ne mure te brendshme	ml	439		
5	2.267/a	Veshje e shkalleve me mermer 3 cm	m ²	19.0		
6	2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama (tarraca)	m ²	326.0		
SHUMA C						
D	PUNIME SUVATIMI VESHJE					
1	2,300	Suvatime solete	m ²	486		
2	2,310	Suvatime mur i brendshem	m ²	1,316		
3	2,331	Suvatim i jashtem i zakonshem	m ²	546		
4	2.404	Boje hidroplastike	m ²	2,348		
5	2.308/a	Suvatim me grafiato h > 4 m	m ²	546		
SHUMA D						
E	PUNIME DYER E DRITARE					
1	2.395/a	Fv dere duralumini me mbushje d/a	m ²	7.60		
2	2.373	F.V. Vetrat duralumini per reception	m ²	6.5		
3	2.395/1	F V dyer d/alumini plastike me dopio xham	m ²	5.67		
4	2.383/2	F V dyer te brendeshme druri importi cilesi e II-te.	m ²	9.45		
1	2.375/a	F.V. Dritare duralumini	m ²	1		
SHUMA E						
F	PUNIME TE NDRYSHME					
1	2,401	Lyerje me boje vaji mbi sip,metalike	m ²	18		
2	2.209	Ulluqe vertikale PWC d.100	ml	50		
3	2.212	Ulluqe horizontale PWC d.101	ml	80		
4	2.273/1	Shtrese pllaka mermeri t = 30 mm	m ²	3		
SHUMA F						

G	PUNIME ELEKTRIKE					
1	2,481/1	Tel PVC 1x1,5	ml	980		
2	2,481/2	Tel PVC 1x2,5 mm2	ml	712		
3	2.48	Tuba plastmasi diam.=11	ml	777		
4	2,480/1	Tuba plastmasi diam.=16	ml	777		
5	2,480/2	Tuba plastmasi diam.=29	ml	138		
6	2.485	Priza brenda murit	Cope	84		
7	2.485	Celsa brenda murit	Cope	28		
8	2.487	Kuti shperndarese diam.=80	Cope	27		
9	2.487	Kuti derivacioni dia.118x96x50 mm	Cope	4		
10	2.a-119	Kuader ndricimi 24 vende	Cope	2		
11	An.5	Ndricues spot tavanor LED me fuqi 20W me	Cope	54		
12	2.a-118	Kaseta elektrike e hyrjes	Cope	2		
13	2.489	Fv. Leshues automatik 16 amp	Cope	10		
14	2.489	Fv. Leshues automatik 10 amp	Cope	10		
15	2.a-120	Fv. llampa sinjali	Cope	2		
16	2.a-107	Fv. mbrojtës diferencial 63 amp	Cope	2		
17	2.a-99	Shirit tokezimi Cu=30*3 mm	ml	10		
18	2.a-74	F.v. Elektroda tokezimi	Cope	1		
SHUMA G						
H	PUNIME HIDROSANITARE					
1	2.504	Komplet wc allafrenga porcelani komplet	Cope	2		
2	2.495	Lavaman porcelani komplet	Cope	2		
3	2.515	F.v pilete dysHEMEJE Ø 50 mm	cope	1		
SHUMA H						
I	SISTEMIME TE JASHTME					
1	3.212	Shtrese çakelli t=10, makadam, perhapur e ngjeshur makineri	m²	200		
2	3.212/b	Shtrese stabilizant t=15cm	m²	200		
3	3.221/1	Shtrese binderi me granil gur kave,4cm,me	m²	200		
4	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m²	200		
6	3.620	Trotuar, me 6 cm beton, me pllaka	m²	25		
7	3.616	F.V Bordura betoni 12x25cm	ml	41		
8	3.24	Shtrese betoni C 12/15 (nen bordure)	m³	0.6		
9	2.426/3	Prishje shtresa betoni	m³	3.0		
SHUMA I						
			SHUMA A-I			
			T.V.SH			
			SHUMA I			
			Supervizioni			
			Kolaudimi			
			SHUMA TOTALE			

Per C.E.C Group
Ing. Vangjush Mbrice
In . Anduen Mbrice