



REPUBLIKA E SHQIPERISE
BASHKIA PRRENJAS

Miratohet:
Kryetari i Bashkise Prrrenjas
Znj.Miranda Rira

PREVENTIVI
Objekti:"STUDIM PROJEKTIM I FUSHES SE FUTBOLLIT, QYTETI PRRENJAS"
BASHKIA PRRENJAS

<i>Nr</i>	<i>Nr Analiz</i>	<i>Pershkrimi i Punimeve</i>	<i>Njesi</i>	<i>Sasia</i>	<i>Cmimi</i>	<i>Vlera</i>
I.PUNIME PER FUSHEN E FUTBOLLIT						
A- PUNIME PER DRENAZHIMIN						
1.0	3.104/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne mjet	m3	7248		
2.0	2.37/1b	Transport dheu me auto deri 6.0 km	m3	7248.0		
3.0	3.183/c	Shtrese zhavor lumi t=20cm	m2	9060.0		
4.0	2.522	Tub drenazhi Ø 170 mm	ml	2108.0		
5.0	2.523	Tub denazhi Ø 200 mm	ml	544.0		
6.0	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	382.5		
7.0	An - 18	Pusete shkarkimi b/a, 50 x 50 cm, h = 100 cm	cope	11.0		
8.0	An-6	FV gjeotekstil 165/m2	m2	9060.0		
9.0	3.184/b	Shtrese zhavor lumi t=40 cm	m2	9060.0		
10.0	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	9060.0		
11.0	3.182/c	Shtrese rere natyrore t=20cm	m2	9060.0		

12.0	An.32	Mbushje me dhe	m3	1359.0		
13.0	3.643	Mbjedhje Bari	m ²	1297.6		
Shuma I					0.0	
II.PUNIME PER KONSTRUKSIONIN E TRIBUNES DHE RRETHIMIN						
1.0	3.104/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne mjet	m3	803.229		
2.0	2.37/1b	Transport dheu me auto deri 6.0 km	m3	720		
3.0	2.262/4	Shtrese betoni C 16/20	m3	175.0		
4.0	2.117/1b	Kollona b/a monolite C 25/30	m3	37.0		
5.0	2.119/1a	Trare e arkitrare b/a C20/25	m3	56.0		
6.0	2.122/1a	Soleta te plota b/a C 20/25	m3	500.0		
7.0	2.166	F V hekur betoni periodik Ø 6 - 10 mm (tribuna qendrore)	ton	4.5		
8.0	2.167	F V hekur betoni periodik Ø > 10 mm (tribuna qendrore)	ton	39.7		
9.0	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	105.0		
10.0	2.182	Konstruksione metalike te thjeshta (kolona D=100mm)	ton	10.0		
11.0	3.837	Rrethim me rrjete teli	m2	900.0		
12.0	3.244/1	Beton C 20/25 (dysHEMEJA)	m3	500		
13.0	2.166	F V hekur betoni periodik Ø 6 - 10 mm (dysHEMEJA)	ton	20.0		
14.0	3.243	Mure betoni C 16/20 (per rrethimin e fushes)	m3	540		
Shuma II					0.0	
III.DHOMA TEKNIKE DHE DHOMAT E ZHVESHJES						
1.0	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	221.322		
2.0	2.37/1b	Transport dheu me auto deri 6.0 km	m3	213.0		
3.0	2.258	Nenshtrese zhavori	m3	35.0		
4.0	2.262/3	Shtrese betoni C 12/15	m3	20.0		
5.0	3.244	Struktura monolite betoni C 20/25	m3	78.0		
6.0	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	6.5		
7.0	2.64/2	Mur me tulle plota ne lartesi deri 3m me llaç perzier M 25	m3	67.0		
8.0	2.122/1a	Soleta te plota b/a C 20/25 t = 10 cm, h ~ 4m	m3	42.0		
9.0	2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama	m ²	336.0		

10.0	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m ²	952.0		
11.0	2.331	Suva e zakonshme fasade mur tulle h ~ 8 m	m ²	621.0		
12.0	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m ²	274.0		
13.0	2.324/b	Plintuse grez importi, h = 10 cm	ml	201.0		
14.0	2.326	Veshje me pllake majolike (per tualetet)	m ²	140.0		
15.0	2.512/4	F.V Kolektor shpendares 1"l kompletuar me sahat	cope	1.0		
16.0	2.491/e	F.V Tuba e rakorderi ujesjellesi PE d=50mm, PN 16 (tubi l furnizimit)	ml	200.0		
17.0	2.491/d	F.V Tuba e rakorderi ujesjellesi PPR d=40mm, PN 16	ml	40.0		
18.0	2.491/c	F.V Tuba e rakorderi ujesjellesi PPR d=20~32mm, PN 16	kg	50.0		
19.0	2.494/5	F.V saracineska bronzi Ø 2 " = 50 mm	cope	3.0		
20.0	2.494/4	F.V saracineska bronzi Ø 1 1/2 " = 40 mm	cope	5.0		
21.0	2.494	F.V saracineska bronzi Ø 1/2 " = 15 mm	cope	36.0		
22.0	2.495	F.V lavaman porcelani importi me mishelator	cope	10.0		
23.0	2.508	F.V bolier 100 liter importi	cope	5.0		
24.0	2.520	Tub kanalizimi pvc Ø 110 mm	ml	100.0		
25.0	2.515	F.V pilete dysHEMEJE Ø 50 mm	cope	13.0		
26.0	2.501	F.V WC allafrenga importi	cope	5.0		
27.0	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	300.0		
28.0	480/2	F.V tub plastmasi Ø 18 ~ 21 mm	ml	110.0		
29.0	2.487/a	F.V kuti suport pllaket 2 modular	cope	8.0		
30.0	2.481/1	F.V percjelles PV-500 Ø 1.5 mm2	ml	15.0		
31.0	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	ml	45.0		
32.0	2.485/2	F.V Çeles 1 polar 220V 10A "Gevis"	cope	10.0		
33.0	2.485/b	F.V priza bivalente 220V 10A 2P-T Gevis	cope	10.0		
34.0	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	ml	249.9		
35.0	2.490/b	F.V Kasete plastike KE me 6 modular (vende)	cope	1.0		
36.0	2.490/1b	F.V Automat termo/el.manj. diferencial 2P 220V, 16A	cope	3.0		
37.0	2.375/a	Dritare d/alumini dhe plastike dyfish xham.	m ²	10.1		

38.0	2.395/a	Dere d/alumini pa xham,me mbushje d/a.	m ²	70.1		
39.0	2.404/1	Boje hidroplastike importi cilesi e I-re	m ²	1815.5		
Shuma III						0.0
	SHUMA (I+II+III)					0
	Fondi Rezerve 5%					0
	SHUMA					0
	T.V.SH 20 %					0
	TOTALI					0

PREVENTIVOI ZENIT 06 SHPK
 ADMINISTRATOR
 REXHEP TARBA

