

PREVENTIV

Objekti: NDERTIM DHE RIPARIM RRUGESH NE BASHKINE KLOS

Nr	Nr Analize	Emertimi i punimeve	Njesia	Sasia	Çmimi	VLERA
I HAPJE AKSI GURRE ,KURDARI , LAGJA MUHARREMI, HAJDINI ,BOZA						
A		HAPJE AKSI RRUGE GURRE LAGJA BOZA E MUHARREMI ,DUKA I MADH				
1	3.101/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , per zgjerim aksi > 2 m, toke zak, kategoria IV, me shk ne toke	m3	103		0
2	3.119/a	Germim shkemb i coptuar me ekskavator 0.5 m ³ , shkemb, ne themele gjeresi ~2 m, me shkarkim ne toke,	m3	45		0
3	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri	m2	200		0
4	3.241	Struktura Shtresa te holla monolite betoni C 12/15 per shtrim rruge Duka I Madh	m3	90		0
5	Analiz treg	Zgare hekuri tel 06 per perdorim ne shtresen e betonit ne rrugen Duka I Madh	m2	200		0
		SHUMA A				0
B		LAGJA LLESHI FSHATI DOM				
1	3.101/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , hapje aksi gjeresi > 2 m, toke zak, kategoria IV, me shk ne toke	m3	17.88		0
2	3.211	Shtrese material cakull mali t=35cm gj=3m	m2	108		0
3	3.122/b	Germim shkemb i coptuar me ekskavator 0.5 m ³ , shkemb, ne themele gjeresi >2 m, me shkarkim ne mjet	m3	2		0
		SHUMA B				0
C		HAPJE AKSI RRUGE LAGJA HAJDINI , ELEZI				
1	3.101/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , per zgjerim aksi > 2 m, toke zak, kategoria IV, me shk ne toke	m3	99		0
2	3.119/a	Germim shkemb i coptuar me ekskavator 0.5 m ³ , shkemb, ne themele gjeresi ~2 m, me	m3	30		0
3	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri	m2	780		0
		SHUMA C				0
D		RIPARIM RRUGA KURDARI LAGJA TOPALLI				
1	3.119/a	Germim shkemb i coptuar me ekskavator 0.5 m ³ , shkemb, ne themele gjeresi ~2 m, me shkarkim ne toke,	m3	15.7		0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri	m2	506		0
		SHUMA D				0

		SHUMA I=A+B+C+D				0
II HAPJE AKSI NE BEJNE						
A		HAPJE AKSI RIPARIM RRUGE SHAHINI BEJNE				
1	3.101/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , per zgjerim aksi > 2 m, toke zak, kategoria IV, me shk ne toke	m3	180		0
2	3.119/a	Germim shkambi i coptuar me ekskavator 0.5 m ³ , shkamb, ne themele gjeresi ~2 m, me shkarkim ne toke,	m3	55		0
3	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri	m2	950		0
		SHUMA A				0
B		HAPJE AKSI RIPARIM RRUGA TEK SHKOLLA VARREZAT				
1	3.101/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , per zgjerim aksi > 2 m, toke zak, kategoria IV, me shk ne toke	m3	191		0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri	m2	334		0
		SHUMA B				0
		SHUMA II=A+B				0
III HAPJE AKSESH						
A		HAPJE RIPARIM RRUGE NE SKARRETH XIBER				
1	3.101/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , per zgjerim aksi > 2 m, toke zak, kategoria IV, me shk ne toke	m3	44		0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri	m2	300		0
		SHUMA A				0
B		HAPJE RIPARIM RRUGE NE QAFE MURRIZE XIBER				
1	3.101/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , per zgjerim aksi > 2 m, toke zak, kategoria IV, me shk ne toke	m3	24		0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri	m2	110		0
		SHUMA B				0
C		HAPJE AKSI RRUGE LAGJIA XHIHERRI KLOS KATUND				

1	3.101/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , per zgjerim aksi > 2 m, toke zak, kategoria IV, me shk ne toke	m3	250		0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri	m2	140		0
SHUMA C						0
D	HAPJE AKSI LAGJIA LLAVESHI FSHAT					
1	3.101/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , hapje aksi gjeresi > 2 m, toke zak, kategoria IV, me shk ne toke	m3	112		0
2	3.211	Shtrese material cakull mali t=35cm gj=3m	m2	108		0
SHUMA D						0
E	HAPJE RIPARIM AKSI LAGJIA ZALL BERSHI (LAGJIA MUCA)- BERSHI					
1	3.101/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , per zgjerim aksi > 2 m, toke zak, kategoria IV, me shk ne toke	m3	40		0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri	m2	500		0
SHUMA E						0
F	HAPJE RIPARIM AKSI LAGJIA SINA FSHAT					
1	3.101/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , hapje aksi gjeresi > 2 m, toke zak, kategoria IV, me shk ne toke	m3	47		0
2	3.211	Shtrese material cakull mali t=35cm gj=3m	m2	392		0
SHUMA F						0
SHUMA III=A+B+C+D+E+F						0
IV RIPARIM RRUGA LAGJIA KROSI, BEL, DOKSANI ÇUPA						
A	Fshati Bel Lagjia Krosi					
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri rruga kryesore dhe degezimet	m2	50		0
SHUMA A						0
B	Fshati Unjate					
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri rruga kryesore dhe degezimet	m2	49		0
SHUMA B						0
C	Fshati Fshat Lagjia Cupa					

1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri rruga e lagjes Laveshi	m2	57		0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri rruga e lagjes Ballosh	m2	29		0
SHUMA C						
D	Fshati Dars,					
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruge Kryesore-lagja Nuraj, Pciri, Losha	m2	41		0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruge kryesore-lagja Mjeshtri	m2	74		0
SHUMA D						
E	Fshati Fullqet,					
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi kroi i Madh lagje Deda	m2	42		0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi Kroi i Madh lagja Dardhaj	m2	58		0
3	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi i rruga kryesore -lagja Halili e Shira	m2	25		0
SHUMA E						
F	Fshati Shengjun					
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi i rrugeve Losha ,Hoxha Hidri ,Beshiri	m2	32		0
SHUMA F						
G	Fshati Plan i Bardhe					
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri rruga auto.- tek shkolla dhe rr kryes fund -1 Allushi	m2	45		0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri rruga automobilistike -qender fshati Shkolla	m2	31		0

3	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri rruga automobilistike -lagja Skordha	m2	20	0
SHUMA G					0
SHUMA IV = A+B+C+D+E+F+G					0
V RIPARIM RRUGESH NE LAGJET E FSHATRAVE BEJNE DHE CERUJE					
A	Fshati Pleshe,				
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruge kryesore lagja Shenkoll + deg. Huta ,Gjini	m2	60	0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruge kryesore-lagja Likaj e Dervishi	m2	25	0
3	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezim rruge kryesore lagja Balaj	m2	62	0
SHUMA A					0
B	Fshati Bershi,				
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri rruga kryesore	m2	52	0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruge kryesore lagjaj Shqarthe	m2	32	0
3	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruge kryesore lagjaj Dani	m2	41	0
SHUMA B					0
C	Fshati Ceruje,				
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri rr. Kryesore Pleshe , Shenkoll -Rrase -Qender Ceruje	m2	38	0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi i lagjes Ftresh Rripe	m2	34	0
3	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri rruga kryesore Pleshe - Kukatin	m2	25	0
SHUMA C					0
D	Fshati Bejne				

1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi shkolla lagja Shahini	m2	58	0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi Shenjatari -Ura e Licit	m2	42	0
3	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruge kryesore lagje Verbare+ Rr Varrezave	m2	39	0
4	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi i lagjes Kllezi	m2	45	0
SHUMA D					0
SHUMA V = A+B+C+D					0
VI RIPARIM RRUGA PATIN ETJ					
A	Fshati Patin,				
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruga kryesore-lagja Pisli	m2	45	0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruga kryesore-lagja Rrema-Tafa	m2	35	0
3	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi i lagjes Vaç	m2	25	0
SHUMA A					0
B	Fshati Dom				
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri rruga kryesore	m2	10	0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi Rruga kryesore lagja Zall -Rripe	m2	30	0
SHUMA B					0
C	Fshati Rripe				
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi Rruga kryesore lagja Pjetraj	m2	35	0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi lagjes Dukaj vogel , Dukaj madhe	m2	35	0

3	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi Rruga kryesore - mali Lezajt	m2	40	0
SHUMA C					0
D	Fshati Gurra e Vogel				
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi Ura e zallit (Lus) Tuneli -Celam	m2	32	0
SHUMA D					0
E	Fshati Gurra e Madhe				
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi Rruga e lagjes Muharrem -Mishter	m2	45	0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi Rruga e lagjes Muslelaj	m2	35	0
SHUMA E					0
F	Fshati Shulbater				
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruga lagjes Gjini - Takajt	m2	25	0
SHUMA F					0
K	Fshati Mishter				
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruga kryes. Ura e deges -Shulimi	m2	30	0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruga Ballazh -Lezaj Siper	m2	20	0
SHUMA K					0
H	Fshati Kurdari				
1	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruga kryes. Ura e Luses-Halilaj	m2	30	0
2	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruga Kurdari-Skenderaj-Hurdhe	m2	25	0
3	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruga Skenderaj -Qaf Dardhe	m2	25	0
4	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruga Spilaj	m2	20	0

5	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruga Kap	m2	20		0
6	3.211	Shtrese cakulli material mbeturine kave t=20cm gj= 3 m perhapur me makineri degezimi rruga Kurdari-Kurqelej	m2	13		0
		SHUMA H				0
		SHUMA VI = A+B+C+D+E+F+K+H				0
		SHUMA I+II+III+IV+V+VI				0
		TVSH				0
		SHUMA TOTALE				0

PREVENTIVUES

MIRATOHET
KRYETARI
BASIR ÇUPA

