

MIRATOHET
KRYETARI I BASHKISË

P R E V E N T I V

OBJEKTI : Rikonstruksion I sheshit "Ismail Qemali" dhe rruga "Veterani"

Nr	Nr.Analiz	PERSHKRIMI	Njesia	Sasia	Cmimi	Vlera
a	b	c	1	2	3	4
		I. PUNIME RRUGE SHESHE				
1	3.197	Prishje shtrese cakulli makineri + trans. deri 10 km	m2	476		
2	2.426/3+2.37/5b	Prishje shtresa shkalle betoni+ trans. deri 10 km	m3	18		
3	3-89/b +2.37/5b	Germim dheu me eskavator rrota goma + trans deri 10 km	m3	127		
4	3-210	Shtrese cakull nyje t= 15 cm + cilindrim perhapur dhe ngjeshur me makineri	m2	1578		
5	3-209	Shtrese cakull nyje t= 10 cm + cilindrim perhapur dhe ngjeshur me makineri	m2	714		
6	3-212/a	Shtrese stabilizanti t=5 cm	m2	2292		
7	2-262/3	Shtrese betoni C 12/15 nen pllaka kunete t=10 cm	m3	22		
8	286+pershtatje	FV pllaka betoni c 25/30 t=8 cm mbi shtrese betoni	m2	219		
9	286 + pershtat.	FV pllaka betoni M-300 t=8 cm mbi shtrese rere	m2	1815		
10	2.266/1	Shtrese pllaka granili me boje	m2	258		
11	3.618	FV bordura betoni C16/20 P.F (20x35)cm mbi beton	ml	135		
12	3-619/a	FV bordura betoni C16/20 P.F (6x20)cm mbi beton kont. Peme	ml	49		
13	3-240	Beton C12/15 per konturim rruge	m3	5		
		SHUMA I	leke			
		II. KANALIZIMI I UJRAVE ATMOSFERIKE				
1	3.89/a+2.37/5b	Germim dheu kanale e puseta+ trans deri 10 km	m3	86		
2	3-An/1t+ persh	F.V tuba plastike te brinjezuar d= 200 mm	ml	247		
3	3.An.164/1b	Mbushje cakull nyje natyrore mbi tub plastik	m3	54		
4	2-An-23	Pusete gratar betoni C16/20, (40x60x100)cm me kapak zgare gize te fiksuar	kompl	12		
5	2-An-19	Pusete betoni C16/20, (80x80x100)cm me kapak gize rrethor Ø 60 cm	kompl	6		
6	Analize	Ngritje puseta ekzistuese te vogla "KUZ"	cope	11		
7	Analize	Ngritje puseta ekzistuese te medha "KUZ"	cope	5		
		SHUMA II	leke			
		VI. PUNIME NDRICIMI RRUGOR				
1	3.45/1+ 3.47/1a	Germim + mbushje kanal linje furnizimi	m3	109		
2	2-480/5	FV tub fleksibel Ø 50mm	ml	405		
3	4.142/2.29	FV kabell elektrik Cu(5x6) mm2	ml	50		
4	4.142/2.29	FV kabell elektrik Cu(5x4) mm2	ml	355		
5	4.142/2.15	FV kabell elektrik Cu(4x2.5) mm2	ml	120		
6	4.142/2.1	FV kabell elektrik Cu(4x1.5) mm2	ml	12		
7	2-a-73	FV elektroda tokezimi xingato e bakerizuar H=1.5 m	cop	4		
8	3-242	Blok betoni C 12/15 per fiksime kantelabri	m3	2.8		

9	3.An/53	FV kantelaber ndricimi H=7 m 250W	komp	8		
10	3.An/53 persht.	FV kantelaber ndricimi xingato H=5 m	komp	7		
11	3An+p	F.v.ndricues "Led" (komplet) 60W	cope	19		
12	4-155/3	FV limitatore 10 A	cop	19		
13	4.155/3	F.v limitator 40A	cope	5		
14	2-490/1e	FV automat 3 fazor 40A	cop	1		
15	2.a-118	FV kasete metalike 36 module	kompl	1		
16	4--59	FV tub celiku Ø 70mm per kalim rruge	kg	54		
17	3.An/pp	F.v. pusete plastike 40x40x40, kapak te forte RIC1084+1086	cope	16		
18	kontrate	Leje lidhje energjie	cop	1		
		SHUMA III				
		SHUMA I- III				
		FOND REZERVE 5%				
		SHUMA III				
		TVSH 20%				
		TOTALI				











