

P R E V E N T I V

OBJEKTI: SISTEMIM ASFALTIM RRUGA "STANKARBUNARE" L=1522m
Njesia Administrative Karbunare e Poshtme LUSHNJE

Nr	N/ an.	Pershkrimi i punimeve	Njesia	Sasia	Çmimi	Vlera
I.SEGMENTI 1 L=565ml b=4ml+ (2x0.5ml)						
1.Punime germimi						
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	130		
2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	130		
					Shuma1	
2.Punime shtresash						
1	3/An-164/1a	Mbushje me cakell ne trupin e rruges	m ³	113		
2	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	2825		
3	3.212/a	Shtrese stabilizanti t=5cm	m2	2825		
4	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	2260		
5	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	2260		
6	2.262/3	Shtrese betoni C12/15 t=8cm	m3	4.5		
					Shuma 2	
3.Punime te KUB						
1	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	ml	36		
					Shuma 4	
4.Punime trotuari						
1	3.617/1	F.V bordura betoni 15x30	ml	100		
2	2262/3	Shtrese betoni nen bordure 10cm	m3	3		
3	2262/3	Shtrese betoni nen trotuar 10cm	m3	16		
4	2.258	Shtrese zhavorr trotuar 10 cm	m3	16		
5	2.266/1	Shtrese pllaka granil me boje 30x30cm	m2	160		
6	3.619/	Bordure fund trotuari 6x20	ml	60		
					SHUMA I	
II.SEGMENTI 2 L=100m b=3ml+ (2x0.5ml)						
1.Punime germimi						
1	3.89/b	Germim dheu me eskavator toke e zakonshme me shk.ne mjet	m3	20		
2	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	20		
					Shuma1	
2.Punime shtresash						
1	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	400		
2	3.212/a	Shtrese stabilizanti t=5cm	m2	400		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	300		
4	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	300		
					Shuma 2	
					SHUMA II	
III.SEGMENTI 3 L=200m b=4ml+ (2x0.5ml)						
1.Punime germimi						
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	52		
2	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	70		
3	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	122		
					Shuma1	
2.Punime shtresash						
1	3/An-164/1a	Mbushje me cakell ne trupin e rruges	m ³	40		
2	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	1000		
3	3.212/a	Shtrese stabilizanti t=5cm	m2	1000		
4	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	800		
5	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	800		
					Shuma 2	
3.Punime te KUB						

1	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	ml	14		
2	2.262/3	Shtrese betoni C12/15 (kanal i hapur)	m3	27		
3	2.258	Shtrese zhavorri t=8cm	m ³	13		
						SHUMA III
IV.SEGMENTI 4 L=657m b=3ml+ (2x0.5ml)						
1.Punime germimi						
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	555		
2	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	295		
3	2.37/4a	Trasport mbeturina ndertimi,dheu deri ne 4km	m3	850		
					Shuma1	
2.Punime shtresash						
1	3/An-164/1a	Mbushje me cakell ne trupin e rruges	m ³	131		
2	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m2	2628		
3	3.212/a	Shtrese stabilizanti t=5cm	m2	2628		
4	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	1971		
5	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	1971		
					Shuma 2	
3.Punime te KUB						
1	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	ml	56		
2	2.262/3	Shtrese betoni C12/15 (kanal i hapur)	m3	84		
3	2.258	Shtrese zhavorri t=8cm	m ³	36		
					Shuma 3	
4.Punime muri mbajtes						
1	3.131/a	Germim shkemb i coptuar me ekskavator 2.0 m ³ , shkemb, ne themele gjeresi ~2 m, me shkarkim ne toke,	m3	813		
2	2.37/4a	Transport dheu auto 5 Km	m3	450		
3	2.258	Shtese zhavorri nen murin mbajtes	m3	19		
4	2.262	Shtrese betoni C 6/10	m3	19		
5	3.321	Mur guri mbajtes e themele, llaç çimento M15	m3	400		
6	2.520	Tub kanalizimi pvc Ø 110 mm	ml	250		
7	3/An.164/1a	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	130		
					SHUMA 4	
					SHUMA IV	
					ShumaI-IV	
					Fond Rez. 2%	
					Shuma	
					Tvsh 20%	
					Totali	

Punoi: Ing.Ariola Dylia

Zyra e projekteve
Ark.Maksim Cuko

Drejtoria e Planifikimit
Ing.Mimoza Haxhiu















