

PREVENTIV

OBJEKTI: SISTEMIM ASFALTIM I RRUGES SUPERSTRADE-PIRAJ

POROSITES: BASHKIA LEZHE

			L = 1200 ml		B= 4 m + 2X0.5	
NR.	Nr.an.	EMERTIMI I PUNIMEVE	NJESIA	SASIA	ÇMIMI	VLERA
A PUNIME NE RRUGE						
1	3.106/b	Germim dheu me eskavator 0.5 m ³ , ne kanale me gjeresi >2m, tok zak ,kategoria IV, ne prezence uji ~2m,me shkarkim ne mjet	m ³	240.0		-
2	3158/5a	Transport materiale ndertimi, deri 5.0 km	m ³	240.0		-
3	An.164/1a	Mbushje me cakull e gur gurorje ne trupin e rruges, perhapur e ngjeshur me makineri 10 cm	m ³	500.0		-
4	3.212 / b	Shtrese stabilizant t=10cm	m ²	6,000.0		-
6	3.228 / 1	Shtrese binderi me zall lavatrice,4cm,me makineri	m ²	5,300.0		-
7	3.233/1	Shtrese asfaltbetoni me zall lavatrice 3cm, me makineri	m ²	5,300.0		-
SHUMA A						
C PUNIME NE VEPRA ARTI						
1	3.106 / b	Germim dheu me eskavator 0.5 m ³ , ne kanale me gjeresi >2m, tok zak ,kategoria IV, ne prezence uji ~2m,me shkarkim ne mjet (nastrimi I skarnatave)	m ³	30.0		-
2	An.164 /1a	Mbushje me cakull e gur gurorje perhapur me makineri (ne skarpaten e ures)	m ³	40.0		-
3	3.245	Struktura monolite betoni C 25/30 per perforcimin e kembeve te ures	m ³	30.0		-
4	2.258	Nenshtrese zhavori	m ³	3.6		-
5	3.366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	m	6.0		-
6	3.243/1	Betoni C16/20, per fiksimit ne hyrje -daljet e tumbinove.	m ³	2.0		-
SHUMA C						
SHUMA A-G						
TVSH 20%						
TOTALI me TVSH						

Hartoi

DREJTORIA E PLANIFIKIMIT DHE ZHVILLIMIT TE TERRITORIT, BASHKIA LEZHE