

PREVENTIV

OBJEKTI: Sistemim asfaltim I rrugeve te brendeshme ne fshatin Tresh

NR.	nr.an.	EMERTIMI I PUNUMEVE	NJESIA	SASIA		
		a, PUNIME GERMIMI				
1	3.106/b	Germim dheu me eskavator 0.5 m3, ne kanale me gjeresi >2m, tok zak ,kategoria IV, ne prezence uji ~2m,me shkarkim ne mjet	m ³	125.0		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	125.0		
		shuma a	leke			
		b, PUNIME NE RRUGE				
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m3	272.0		
5	3.212/b	Shtrese stabilizant t=10cm	m2	2,330.0		
7	3.228/1	Shtrese binderi me zall lavatrice,4cm,me makineri	m2	1,860.0		
8	3.231/1	Shtrese asfaltobetoni me zall lavatrice, 3cm, me makineri	m2	1,860.0		
		shuma b	leke			
		c, PUNIME NE TROTUARE				
1	3.110/b	Germim dheu me eskavator me zinxhire 1.0m3, ne kanale me gjeresi >2m, tok zak ,kategoria IV, ,me shkarkim ne mjet (per ndertimin kasonet)	m ³	12.0		
2	3.158/5a	Transport materiale ndertimi, deri 5.0 km	m ³	12.0		
3	2.258	Mbushje me Nenshtrese zhavori 25cm	m ³	65.0		
5	3.212/b	Shtrese granili 7cm, me makineri	m ²	260.0		
6	3.620	Trotuar me 6 cm beton, me pllaka	m ²	260.0		
7	3.243/1	Beton C16/20, per kuneta	m ³	10.0		
8	3.242	Beton C12/15, per bordurat	m ³	8.0		
10	3.617/1	F V bordura betoni 15x30 cm	m	130.0		
		shuma c	leke			
E		PUNIME PER NDRICIMIN RRUGOR				
1	3.An/1sh	F.V. Shtylle metalike konike ndricimi H=9ml. PAICC-3	cope	7.0		
2	3.An.1	F.V.ndricues LED 60W	cope	7.0		
3	3.An/ksh	F.V. krah shtylla metalike KRH -MSI 1500/1500/10	cope	7		
4	3.An/et	F.V. Elektroda tokezimi te zinkuara 50x3mm, L=150cm	cope	7.0		

5	AN.EL3	F.V. Kabell FG7OR 0.6/ 1KV. 5x10.0mm ²	ml	130.0		
6	AN.EL5	F.V. Kabell FG7OR 0.6/ 1KV. 4x2.5mm ²	ml	130.0		
7	2.a-93	Percjelles togezimi bakri ,CU, S=35mm ²	ml	7.0		
8	3.An/pp	F.V. Puseta plastike 40x40x40mm me kapak te forte RIC 1084+1086	cope	7.0		
9	An.e15	F.V. Tub fleksibel me 2 shtresa D=90mm	ml	130.0		
10	An.17	F.V. Kuader komandimi per ndricimin rrugor santeri+fotoelement	cope	1.0		
11	An.e18	F.V. Puseta betoni me Kapak Gize 100x100x100cm	cope	7.0		
12	AN.48	F.V. Tub metalik D=140mm	ml	130.0		
13	2.262	Shtrese rere nen dhe mbi tuba	m ³	1.0		
14	2.262	F.V. Beton M-100 mbi tuba	m ³	2.0		
15	2.258	Mbushje me Nenshtrese zhavori	m ³	5.0		
16	3.89/a	Germim dheu me eskavator me goma 0.25m ³ , ne kanale me gjeresi deri 2m,toke zak, kat III, me shkarkim ne mjet	m ³	21.0		
17	2.262/3	Shtrese betoni C12/15 , per betonimin e shtyllave	m ³	3.5		
SHUMA E						
d, PUNIME NE KUB						
1	3.106/b	Germim dheu me eskavator 0.5 m ³ , ne kanale me gjeresi >2m, tok zak ,kategoria IV, ne prezence uji ~2m,me shkarkim ne mjet	m ³	12.0		
2	2.258	Nenshtrese zhavori	m ³	3.0		
4	3.An/2t	F.V. tub PVC Ø400 mm per linjat e jashtme	ml	-		
5	An - 22/1	Pusete shiu 40x40,h=100cm, me kapak gize	cope	4		
6	An - 18	Pusete shkarkimi b/a 50x50cm, h=100cm	cope	1		
shuma d			leke			
SHUMA A-E			Leke			
TVSH 20%			Leke			
TOTALI			Leke			

Ing. Gjovalin Marku