



REPUBLIKA E SHQIPËRISË
BASHKIA PRRENJAS



PREVENTIV

Objekti: "Ndertim rrjetit te kanalizimeve te ujrave te zeza Lagja e ish zyrat e Ndermarrjes se Kromit, Qyteti Prrenjas Bashkia Prrenjas.

Nr	Analiza Teknike	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
A		PUNIME GERMIMI				
1	3.59/c	Germim themel i vecuar, gropa sip. 10-30 m ² , toke e forte me h=1.5m	m3	226.0		
2	2,48/an	Germim shkemb I forte me cekic me eskavator me zinxhir	m3	1,520.0		
3	3.46/1	Germim kanalesh me krah ne toke te forte me sek deri 0.75 m2	m3	277.0		
4	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	892.0		
5	3,An/2t	FV tubo te brinjeezuar HDPE sn8 D=400mm	ml	815.0		
6	An - 20	Pusetete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	41.0		
7	2.575	Puse kontrolli 1x1x1.5m	cope	3.0		
8	3.353	Mbushje me shkemb te germuar me pare	m3	733.0		
9	2.258	Mbushje me zhavor	m3	550.0		
10	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m3	1,290.0		
11	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m2	3,026.0		
12	3.212/b	Shtrese stabilizant t=10cm	m2	470.0		
		SHUMA A				
B		PUNIME PRISHJE				
1	2.426/3	Prishje shtresa betoni	m3	55		
2	An	Skarifikim shtrese asfalti me makineri (prerje asfalti)	m2	16		
3	3.620	Trotuar, me 6 cm beton, me pllaka	m2	25		
4	3.617/1	F V bordura betoni 15x30 cm	ml	27		
5	3.215	Asfaltim me penetrim 6.5 cm me dy shtresa me makineri	m2	18		
6	2.52/2	Mur guri themel e xokol me llaç perzier M 25	m3	3		
		SHUMA B				
		SHUMA pa TVSH				
		Fondi rezerve 5 %				
		SHUMA				
		TVSH 20%				
		SHUMA TOTALE				